

HISTORIC PRESERVATION COMMISSION

Marc Elrich
County Executive
Chair

Date: 1/14/2025

MEMORANDUM

TO: Rabbiah Sabbakhan

Department of Permitting Services

FROM: Laura DiPasquale

Historic Preservation Section

Maryland-National Capital Park & Planning Commission

SUBJECT: Historic Area Work Permit # 1050805 – Revisions to previously-approved foundation cladding on

new house and tree removal

The Montgomery County Historic Preservation Commission (HPC) has reviewed the attached application for a Historic Area Work Permit (HAWP). This application was **approved with two (2) conditions** at the January 8, 2025 HPC meeting:

- 1. The same stamped concrete must be used around the base of the entire main block, including the front elevation. The porch cladding may remain as proposed.
- 2. Pictures of the specific trees to be removed will be provided to staff.

The HPC staff has reviewed and stamped the attached submission materials.

THE BUILDING PERMIT FOR THIS PROJECT SHALL BE ISSUED CONDITIONAL UPON ADHERENCE TO THE ABOVE APPROVED HAWP CONDITIONS AND MAY REQUIRE APPROVAL BY DPS OR ANOTHER LOCAL OFFICE BEFORE WORK CAN BEGIN.

Applicant: Danilza Garcia

Address: 19820 White Ground Road, Boyds

This HAWP approval is subject to the general condition that the applicant will obtain all other applicable Montgomery County or local government agency permits. After the issuance of these permits, the applicant must contact this Historic Preservation Office if any changes to the approved plan are made. Once work is complete, the applicant will contact Laura DiPasquale at 301-495-2167 or laura.dipasquale@montgomeryplanning.org to schedule a follow-up site visit.







APPLICATION FOR HISTORIC AREA WORK PERMIT HISTORIC PRESERVATION COMMISSION 301.563.3400

APPLICANT:

| Name: | E-mail: | | | |
|--|---|--|--|--|
| Address: | City: | Zip: | | |
| Daytime Phone: | Tax Account No.: | | | |
| AGENT/CONTACT (if applicable): | | | | |
| Name: | E-mail: | | | |
| Address: | City: | Zip: | | |
| Daytime Phone: | Contractor Regist | tration No.: | | |
| LOCATION OF BUILDING/PREMISE: MIHP # of h | listoric Property | | | |
| Is the Property Located within an Historic District' Is there an Historic Preservation/Land Trust/Envi map of the easement, and documentation from t Are other Planning and/or Hearing Examiner App (Conditional Use, Variance, Record Plat, etc.?) If Y supplemental information. Building Number: Street: | No/Individual Site I conmental Easement on he Easement Holder sup rovals /Reviews Require ES, include information | Name the Property? If YES, include a poorting this application. ed as part of this Application? on these reviews as | | |
| Town/City: Neares | t Cross Street: | | | |
| Lot: Block: Subdivided Subdivided Block: Subdivided Bl | on Page 4 to verify th | at all supporting items | | |
| be accepted for review. Check all that apply: New Construction Deck/Porch Addition Fence Demolition Hardscape/ Grading/Excavation Roof I hereby certify that I have the authority to make and accurate and that the construction will compagencies and hereby acknowledge and accept the Danilza Garcia | ☐ Sho ☐ Sol ☐ Tre Landscape ☐ Wii ☐ Oth the foregoing application | ed/Garage/Accessory Structure lar ee removal/planting ndow/Door ner: on, that the application is correct and approved by all necessary | | |

| Description of Property: Please describe the building and surrounding environment. Include information on significant structures, landscape features, or other significant features of the property: |
|--|
| |
| |
| |
| |
| Description of Work Proposed: Please give an overview of the work to be undertaken: |
| |
| |
| |
| |
| |
| |
| |
| |
| |
| |

| Work Item 1: | |
|-----------------------------------|----------------|
| Description of Current Condition: | Proposed Work: |
| | |
| Work Item 2: | |
| Description of Current Condition: | Proposed Work: |
| Work Item 3: | |
| Description of Current Condition: | Proposed Work: |

JAIME & DANILZA GARCIA

19820 WHITE GROUND ROAD BOYDS, MARYLAND 20841

(c) 2018

DAVID R. ROBBINS EXPRESSLY RESERVES ITS COPYRIGHT AND PROPERTY RIGHTS IN THESE PLANS AND DRAWINGS. THESE PLANS AND DRAWINGS ARE NOT TO BE REPRODUCED IN ANY FORM OR MANNER.

"GARCIA RESIDENCE"

MONTGOMERY COUNTY

| | 'LINDEN' Square Footages | |
|------------|---------------------------|----------------|
| | Area | Square Footage |
| <u>a</u> | First Floor | 1926 SF |
| FINISHED | Second Floor | 1807 SF |
| 18 | Total (First & Second) | 3733 SF |
| 匝 | | |
| | | |
| | Garage | N/A |
| UNFINISHED | | 1648 SF |
| ∣≌ | Basement Utility/ Storage | 152 SF |
| 불 | Total (Unfinished) | 1800 SF |
| | | |
| | Foyer | 6' X 13'-6" |

WINDOW MANUFACTURE: SILVERLINE **SERIES: 2900**

ALL WORK SHALL COMPLY WITH 2018 INTERNATIONAL RESIDENTIAL CODE W/ AMENDMENTS WALL BRACING SHALL BE IN ACCORDANCE WITH ENGINEERED DESIGN and CONTINUOUSLY SHEATHED W/ 1/16" WOOD SHEATHING FLOOR FRAMING TO BE 2 x 12 FLOOR JOISTS @ 16" O.C. OR 12" O.O. (AS NOTED) -HEM FIR #2 - Fb=978 psi (OR BETTER)

" THE LOCAL JURISDICTION SHALL FILL IN THIS TABLE WITH LOCAL CLIMATIC AND GEOGRAPHIC CRITERIA "

| 2018 | 018 CLIMATIC AND GEOGRAPHIC DESIGN CRITERIA: | | | | | | | М | ONTGOMER" | Y COUNTY MA | ARYLAN | D | |
|---------------------|--|-------------|--------------------------|-------------|-------------------|------------|------------------------|-------------------|-----------|---|--------------|-------|-------|
| GROUND SNOW LOAD | Speed | Topographic | D DESIGN Special Wind | Windborne | SEISMIC DESIGN | | SUBJECT TO DAMAGE FROM | | | DESIGN UNDERLAYMENT FLOOD HAZARDS FREEZ | | | |
| SNOW LOAD | (mph) | Effects | Region | Debris Zone | CATEGORY | Weathering | Frost Line Depth | Termite | TEMP. | REQUIRED | | INDEX | TEMP |
| 3Ø PSF | 115 | В | | | A/B | SEVERE | 30" | MODERATE TO HEAVY | 13° F | YE5 | JULY 2, 1979 | 300 | 55° F |

| Sheet List Table | | | | |
|------------------------------|-----------------|--|--|--|
| SHEET ARCHITECTURAL DRAWINGS | | | | |
| 001 COVER SHEET | | | | |
| 002 | GENERAL NOTES | | | |
| EC1 | THERMAL | | | |
| A301 | FRONT ELEVATION | | | |
| A302 | LEFT ELEVATION | | | |
| A303 | REAR ELEVATION | | | |
| A304 | RIGHT ELEVATION | | | |
| A401 | FOUNDATION | | | |
| A501 FIRST FLOOR | | | | |
| A601 SECOND FLOOR | | | | |
| A701 | WALL SECTION | | | |
| A801 | SECTION A-A | | | |
| A802 | SECTION B-B | | | |
| A803 | SECTION C-C | | | |
| E101 | ELECTRICAL_1ST | | | |
| E201 | ELECTRICAL_2ND | | | |
| S101 | FRAMING_1ST | | | |
| S201 | FRAMING_2ND | | | |
| S301 | ROOF FRAMING | | | |
| S401 | LATERAL DETAILS | | | |
| S402 | LATERAL_FOUND | | | |
| S403 | LATERAL_1ST | | | |
| S404 | LATERAL_2ND | | | |
| | | | | |
| | | | | |

| REVISIONS | | | | | |
|------------|-----------------------------------|-----|--|--|--|
| DATE | COMMENTS | BY | | | |
| 02-26-2019 | MID-POINT | SJS | | | |
| 04-23-2019 | TOLL BROTHERS REVIEW | SJS | | | |
| 06-07-2019 | PERMIT SET | ACI | | | |
| 09-26-2024 | GARCIA RESIDENCE MID-POINT REVIEW | TPF | | | |
| 10-30-2024 | FINAL REVIEW | TPF | | | |
| 12-2-2024 | PERMIT SET | TPF | | | |
| | | | | | |

REVIEWED

By Laura DiPasquale at 9:42 am. Jan 14, 2025

| Professional | Certifica | tion_ |
|---|--|-----------|
| I hereby certify were prepared of that I am a dul professional Arci of the State of | r approved y licensed hitect under | by me, an |
| license number | 5921 | |



Architecture Collaborative, Inc. 8334 Main Street Ellicott City, MD 21043

ArchitectureCollaborative.com Fax: (410) 465-0903 Tel.: (410) 465-7500

GENERAL NOTES

- · ALL WORK SHALL COMPLY TO ALL APPLICABLE LOCAL CODES.
- · All construction shall be classified as One- and Two-Family Dwellings and comply to the 2018 INTERNATIONAL RESIDENTIAL CODE w/
 AMENDMENTS.
- · All construction shall comply to the 2018 INTERNATIONAL ENERGY CONSERVATION CODE (or as required by local code)
- These plans and notes are the property of Architecture Collaborative, Inc. Use of these plans without the written consent of Architecture Collaborative, Inc. is prohibited
- · These are conceptual plans and schematic in nature. Their purpose is to develop a proto-type house.
- These plans are subject to modification as necessary to meet code requirements or to facilitate mechanical/plumbing installations or to incorporate design improvements. The Architect reserves the right to make any changes, for any reason, at any time,
- The Owner shall defend, indemnify and save harmless the Architect. and Architecture Collaborative, Inc. from and against all suits, actions claims, liabilities, losses and/or expenses, including attorneu's fees, arising out of or resulting from the performance of any work by the Owner or its employees, subcontractors, agents or representatives, caused in whole or in part by any act or omission, whether negligent or otherwise, on the part of the Owner or its employees, subcontractors, agents or representatives.
- The Contractor shall compare and coordinate all drawings. When a discrepancy or an error/omission exists, he shall comply with the code and contact the Architect and Owner in writing for proper adjustment.
- · These plans are NOT to be scaled for Construction purposes. Written dimensions and notes supercede all scale references. Contact the Architect and Owner prior to work when any discrepancy arises.
- In the event certain features of construction are not fully shown on the drawings, their construction shall be of the same character as for similar conditions that are shown or noted
- · Habitable space, hallways, and portions of basements containing these spaces shall have a ceiling height of not less than 7'-0" except as required by code.
- * Beams, girders, ducts or other obstructions in basements containing habitable space shall be permitted to project to within 6'-4" of the
- Integral garages in dwelling units shall be separated from all adjacent living space w/ fire separation as required by local code.
- * These drawings do not include structural details.

DESIGN LIVE LOADS

30 PSF (40 PSF per JURISDICTION) Sleeping Floors 30 PSF Living Floors 40 PSF Attic Floors 30 PSF 40 PSF Exterior Decks 50 PSF Garage Slabs Exterior Balcony's 40 PSF

40 PSF Individual treads designed for uniformly distributed live load or 300-bound concentrated load over a 4 square inch area. whichever produces greatest stress.

Guard Rails 200 LB A single concentrated load applied in any direction at any point along the top.

SITE

- GENERAL: These drawings do NOT cover sitework, grading, landecapina or zonina
- Building foundations have been designed based on an assumed soil bearing capacity of 2,000 PSF (or as noted). Additional engineering may be required if soil bearing capacity is less than 2,000 PSF (or as noted), or if there is no Geotechnical report
- In lieu of a complete geotechnical evaluation, load-bearing values per Table R40|41 shall be assumed
- Provide continuous perimeter foundation drainage in accordance with local code requirements. Where both interior and exterior drains are required, provide minimum 1-1/2" dia. bleeder pipes through mid-line of footing at 8' o.c. (max.). Tupically, drains shall be lead to sump pits or to positive daylight discharge points.
- · Slope all stoops, porches, walks and garage slabs away from building 1/8" minimum per foot
- · All work shall comply with local codes.

STAIR NOTES

- · INTERIOR and EXTERIOR STAIRS
- All stairs shall comply with the code and all local amendments.
 Minimum finish width: 36"
- Minimum finished headroom height: 6'-8"
 Maximum riser height to be 7 3/4" or per local code.
- = Minimum tread depth to be 10" or per local code. = Maximum space between ballisters to be 4" or per local code.
- = Handrail height shall NOT be less than 34" or greater than 38" and may not project more than 3 1/2" into stair width
- . Stair winders shall have a minimum inside width of 6" and a minimum tread (10") or as per code, when measured 12" from the inside corner
- \cdot Stair landings shall be a minimum of 36" x 36" finished.
- · Stairwaus with (3) or more risers are required to have a handrail.
- · Guard rails:
- Porches, balcony's or raised floor surfaces located more than 30" above the floor or grade below shall have guard rails not less than 36" in height. Guard rail spacing shall be designed not to allow passage of an object of 4" or more in diameter
- The stair manufacturer is responsible for the design and construction of the stair. All work shall comply with local code.

CONCRETE

- Bottom of footings shall be located at minimum frost line below finished grade, as per local code. Steps or depth of footing/ foundation may vary according to local site or frost condition
- All interior concrete slabs 30'-0" or greater in any direction shall have 6"x6"x#10 welded wire mesh or control joints. Monolithic turned down slabs for Townhouses shall have a control joint between units when required by local code.
- · Concrete used in exposed areas implicit to freezing and thawing (both during construction and service life) shall be air-entrained accordance with local code. Exterior flat-work shall be coated with an approved curing compound.
- · Foundation walls of habitable space located below grade shall be water-proofed or damp-proofed using materials and methods approved by the local building jurisdiction.
- · Garage / Exterior slabs shall be 5% to 7% air entrained concrete.

| Construction: | Compressive Strength: |
|-------------------------|-----------------------|
| Footings | 2.500 PSI (MIN.) |
| Foundation Walls | 3, 000 PSI |
| Interior Concrete Slabs | 3 000 PSI |
| Garage Slabs | 3,500 PSI |
| Exterior Concrete Slabs | 3,500 PSI |
| (as per local code) | |

· The concrete contractor is responsible for the design and construction of all concrete work. All work shall comply with code

MASONRY

 The maximum vertical distance of unbalanced fill measured from the top of the lower level floor slab to outside finished grade, shall not exceed the following and shall be re-inforced with 5 bars a 16" o.c.

| rioigni or riii |
|-----------------|
| 4'-Ø" |
| 5'- Ø " |
| 6'-0" |
| 5'-Ø" |
| 7'-Ø" |
| |
| |

- Presumptive Load-Bearing Values of Foundation Materials shall not be less than 2,000 PSF or greater than 60 PCF lateral pressure. Additional engineering may be required if lateral pressure or load-bearing values are not within the above values.
- All backfill shall consist of sand and/or gravel.
- Top courses of CMU, foundation walls shall be filled solid, including the courses under any steel beam or corbelled CMU, as per local
- Stone and Masonry veneer shall be attached and anchored in accordance with Section 103 (with Amendments).
- The masonru contractor is responsible for the design and construction of all masonry work. All work shall comply with local codes.

SPECIALTIES

- Pre-Built fireplace units shall be UL approved and installed according to code and manufacturers specifications and
- Wood burning fireplaces shall have tight-fitting flue dampers and
- · Chimneys shall extend a minimum of 2'-0" above any roof structure
- Provide overflow pans and drains for wet appliances when located
- Provide a 22"x30" (Min.) attic access with switched light or 22"x48" pull down stair. Seal and insulate as per local cod
- Kitchen and Bath plans are approximate. See manufacturers plans for exact layout and dimensions
- · The drywall contractor is responsible for the design and construction of the party walls, fire walls and fire separation assemblies. All work shall comply with local codes
- The fire suppression contractor is responsible for the design and construction of the suppression systems. All work shall comply with

THERM. PROTECTION

| R-Value: | Thickness: | Location: |
|-------------------------|-------------------|-----------------------------------|
| R-4.6 | | Duct Insulation in uncond. sp. |
| R-6 | | Duct insulation in uncond. sp. |
| R-6 | | Duct insul. below conc. slab. |
| R-8 | | Duct Insulation in Attic. sp. |
| R-10 | 2" | Slab Insulation at Perimeter |
| R-11 (blanket) | 3.5" | Basement Walls - Unfinished |
| R-13 | 3.5" | Basement Walls - 2x4 Finished |
| R-13 + 5 | 3.5" | 2x4 Walls - Exterior |
| R-21 | 5.5" | 2x6 Walls - Exterior |
| R-19 | 6.25" | Crawl space / Floors exposed |
| | | to unconditioned space |
| R-3Ø | 12" | Ceiling (w/ Energy heel) |
| R-38 C | 1025" | Vaulted Ceiling |
| R-38 | 12" | Ceiling (w/ Energy heel) |
| R-49 | 15" (min.) | Ceiling (w/ standard heel) |
| * When using blown insu | ulation, the manu | ifacturer's settled R-value shall |

- be used and the blown insulation shall be installed per manuf. specs
- The building thermal envelope shall meet the requirements of the IECC Sections R402.1.1 through R402.1.5.
- · Prescriptive R-values in IECC Table R402.12 are shown above. • Per IECC Section R402.1.4, Alternate U-values of an assembly may be substituted as the U-factor Alternative method to meet building thermal envelope requirements.
- Per IECC Section R402.15, the Total UA Alternative method may be used to meet the building thermal envelope requirements.
- Insulation for slab-on-grade construction shall begin at the inside intersection of the slab and foundation wall and shall extend for a minimum distance of 24" down the inside face of the foundation wal and horizontally under the slab.
- Provide continuous soffit vents and ridge ventsas shown on drawings and as per code. Install insulation baffles in accordance with local code, in each truss/rafter bay to maintain free air flow.
- Flashing shall be of pre-finished aluminum (or equal), installed at all roof offsets, chimneys, roof openings, hips, valleys, ridges, dormers and where roof intersects wall (as per local code).
- Contractor shall maintain, in all instances, proper fire, sound and insul. ratings when penetrating through walls, floors, ceilings and roofs.

METAL

- · Straps/bolts shall be per code and building inspector approved:
- Min. (2) straps/bolts per section of plating 12" max. from each end with intermediate straps/bolts at:
- 1/2" bolts spaced per code
- Straps spaced per code or per manuf.'s spec.'s
- Galvanized metal brick ties shall be installed as per local codes.
- * Gutters, downspouts, and bleeders shall be installed by the contractor as required by local codes
- All structural steel shall be detailed, fabricated and erected in accordance with the latest edition of AISC (American Institute of Steel Construction) "Specification for Structural Steel Buildings -Allowable Stress Design and Plastic Design" and AISC code of standard practice, shall be of domestic origin and conform to:
- Wideflange = ASTM A992, Fu = 50 ksi
- Plates and Angles = ASTM A36 HSS Round ASTM A53, Grade B Fu = 35 ksi

WINDOWS and DOORS

- Provide safety glazing as required by local code.
- * All doors and windows shall be sealed and flashed on all sides and installed in accordance with manufacturers specifications and per
- Garage door into dwelling shall have a minimum fire rating of 20 minutes (or per local code). The threshold of the door opening between the garage and adjacent interior space shall not be less than 4" above the garage floor (or per local code).
- · Every sleeping room shall have at least one operable window o exterior door approved for emergency egress or rescue. The sill height shall not be more than 44" above the floor. Egress windows must have a minimum net clear opening of 5.7 ft 2 , or per local code.
- Window sill height shall be a minimum 24" above finished floor at all sills greater than 72" above finished grade, or per local code.

WOOD

- Wall bracing shall be installed as per local code.
- * All roof trusses and floor systems shall be engineered by others.
- * All roof trusses and floor sustems shall be braced and installed be manufacturers specifications and per local code. See manufacturers plans for exact layout and construction.
- * Fire-stopping shall be provided to cut off concealed draft openings and to form an effective fire barrier between stories, as
 - At the intersection of Kitchen bulkhead and wall.
 - At the top of all heat chases
 - At bathtub trap openings.
 - 2x fire-stopping / blocking at every floor or 8'-0" o.c. vert.
- * LVL Beams: 1-3/4" wide 20E Microlam LVL
- * LSL Beams: 3-1/2" wide 1.55E Timberstrand LSL PSL Beams: 3-1/2" wide - 2.0E Parallam PSL
- PSL Columns: (as noted) 1.8E Parallam PSL Column
- * All walls to be 16" o.c. (stud thickness per plan), minimum SPF stud grade unless otherwise noted. Interior non-load bearing partitions
- · All interior and exterior load bearing walls shall have lapping top plates where walls intersect
- ^a All wood less than 8" from grade shall be treated lumber. All sole plates on slabs and foundations shall be treated lumber
- Provide bearing at all structural members as required by code.
- · Provide floor and wall blocking as shown on framing plans as required by local codes
- See drawings for type of floor construction. - Tongue and groove floor decking, glued and fastened on floor joists shall meet the American Plywood Assoc. Sturd-I Floor System.
- * All materials shall be installed per manufacturers specifications and per applicable local codes

MECH. PLUMB. ELEC.

- Mechanical contractor is responsible for the design and installation of the mechanical systems including duct sizes, trunk and register sizes for air conditioning, heating and ventilation. Systems shall be installed per manufacturers specifications and recommendations and per all applicable codes
- Mechanical systems shall provide a minimum of (3) air exchanges per hour (or per local code). The building shall be provided with ventilation that meets the requirements of the International Residential Code or International Mechanical Code, as applicable
- Per IRC R303.4, when the air infiltration rate of a dwelling unit is 5 air changes per hour or less, the dwelling unit shall be provided with whole-house mechanical ventilation in accordance with IRC section MI5073. Outdoor air intakes or exhausts shall have automatic or gravity dampers that close when the ventilation system is not
- Mechanical sustems in unconditioned space shall have a manufacturer's designation for an air leakage of no more than 2% of the design air flow rate when tested in accordance w/ ASHRAE 193.
- Plumbing contractor is responsible for the design and installation of plumbing and piping. All plumbing, piping and fixtures shall be installed per manufacturers specifications and recommendations and per all applicable codes.
- * Each Sump shall be sealed and vented as per code, vented through roof with 3" Diameter vent.
- Electrical contractor is responsible for the design and installation of all electrical systems. All electrical work shall meet the requirements of the National Electric Code, the local power company and all applicable codes. Fixtures and apparatus are selected by the builder and shall be UL approved.
- Install programmable thermostats
- Smoke detectors and Carbon Monoxide detectors:
 - Provide a minimum of (1) ceiling mounted fixture per floor, hard wired to a nearby circuit and interconnected for simultaneous activation with battery backup.
 - Provide Smoke detectors at each sleeping room.
- * Not less than 90% of the lamps in permanently installed lighting fixtures shall be high efficiency lamps or not less than 90% of permanently installed lighting fixtures shall contain only high-efficiency
- Sprinkler system (when required) shall be NFPA-13D, installed per manufacturers specifications and recommendations and per all applicable local codes.
- *Floor assemblies such as manufactured 1-Joist or open web joists, other than minimum 2x10 dimensional lumber or structural composite lumber, located directly over a space that is not protected by an automatic sprinkler sustem shall be protected by 1/2" gupsum board to the underside of the TJI floor framing members, or other code approved method.

| TABLE 103.8.3.1 | b,c,d | | | | |
|---------------------------------|--------|--------------------|----------------------|---|--|
| SIZE OF STEEL ANGLE (inches) | | ONE STORY ABOVE | TWO STORIES ABOVE | NO. OF 1/2" (OF EQUIVALENT) REINF. BARS | |
| 3 × 3 × 1/4 | 6'-0" | 4'-6" | 3'-Ø" | 1 | |
| 4 × 3 × 1/4 | 8'-0" | 6'-0" | 4'-6" | 1 | |
| 5 × 3 1/2 × 5/16 | 10'-0" | 8'-0" | 6'-0" | 2 | |
| 6 × 3 1/2 × 5/16 | 14'-0" | 9'-6" | 1'-0" | 2 | |
| 2-6 × 3 1/2 × 5/16 | 20'-0" | 12'-Ø" | 9'-6" | 4 | |

For SI: I inch = 25.4 mm , I foot = 304.8 mm

- a. Long leg of the angle shall be placed in the vertical
- Depth of the re-inforced lintels shall not be less than 8" and all cells of hollow masonry lintels shall be grouted solid. Re-inforcing bars shall extend not less than 8" into the Steel members indicated are adequate tupical examples
- Other steel members meeting structural design requirements may be used.
- d. Either steel angle or re-inforced lintel shall span opening

REVIEWED

By Laura DiPasquale at 9:42 am, Jan 14, 2025

Historic Preservation Commissio

Karen Bulit

APPROVED

Montgomery County

2018 IRC - 2018 IECC

SHEET # 002 doc by 1 the 12/2/2024 9:50 AM

Architecture Collaborative, Inc.

12/2/2024 9:50:33 AM, Architecture Collaborative, Inc.

JAIME

laborative, Ellicott City, MD

Colle

hitecture

Arc.

e: 10/13/

GARCIA

ZA

DANIL

શ્ર

(34x22) file: (17x11) 2.0

scale: U.N.O.


St


8334

City,


Ellicott com


(410)








JAIME





























SLF date: 10/13/18


GARCIA $S_{0.77}^{e=4}$ (34x22) lile: drawn: $S_{0.77}^{e=4}$ (77x11) 8.3 drawn: $S_{0.77}^{e=4}$ (AZA (CARCIA RESIDENCE SHEET # A803 Architecture Collaborative, Inc. 12/2/2024 9:51 AM


Collaborative,
Ellicott City, MD &


Architecture 8334 Main Street





SLF date: 10/13/18
GARCIA DANILZA JAIME & DA JAIMESHEET # E101 Architecture Collaborative, Inc.











GABLE END TRUSS SHEATHED -WOSB/PLYWOOD

FASTEN BOTTOM CHORD OF

GABLE END TRUSS TO DBL.

3"x0.131" NAILS @ 8" O.C. OR

3"x0.120" NAILS @ 6" O.C

(SEE PLAN)

HEEL HEIGHT LESS THAN 4½" NO BLOCKING REO'D

PROVIDE GABLE

END BRACING


PER TRUSS
MANUFACTURER


AND/OR BOSI

2x10 (9½" - 12" HEEL) OR 2x12 (12" - 16" HEEL) SOLID BLOCKING PANELS EVERY MAX) FASTEN EA, BLOCKING PANEL TO TOP PLATE W (4) 3"x0 |3|" TOFNAII 5 OR BLOCKING MUST FIT TIGHT (5) 3"x0.120" TOENAILS -BETWEEN TRUSSES. FASTEN EA. END OF (2) 3"x0.120" TOENAILS @ TOP 2x EXT. WALL: TOP PLATE OF WALL WITH 'SIMPSON' H2.5T CLIP &


TYPICAL SHEAR

TRANSFER DETAIL @ ROOF HEEL HEIGHT SETVEEN 4½" - 16" BLOCKING REO'D






TYPICAL SHEAR TRANSFER DETAIL BETWEEN FLOORS @ EXTERIOR WALL



TYPICAL SHEAR TRANSFER DETAIL @ EXTERIOR BASEMENT WALL



TYPICAL SHEAR TRANSFER

A3 DETAIL @ RAISED HEEL TRUSS

OSB/PLYWOOD SHEATHING

UP VERTICALS OF ROOF TRUSSES, & FASTEN W

- FASTEN ROOF TRUSS TO

TOP PLATE OF WALL WITH 'SIMPSON' H2.5T CLIP \$

(4) 3"x0.131" TOENAILS OR

2x EXT. WALL-

23/8"x0.113" NAILS @ 6" O.C.

TYPICAL SHEAR TRANSFER DETAIL @ EXTERIOR GARAGE WALL

LEDGER w/ 2%"x 0.113" NAIL5 o 6" O.C. FASTEN 2x6 LEDGER OR TOP -2x EXTERIOR SHEAR WALL ABOVE NSTALL SHEATHING-ASTEN SOLE PLATE OF PRIOR TO INSTALLING LOW ROOF TRUSSES SHEARWALL TO RIM BOARD W 3"x0.131" NAIL5 @ 6" O.C. LOW ROOF TRUSSES RIM BOARD FASTENED TO DBL (SEE PLAN) -2x INTERIOR SHEAR TYPICAL SHEAR TRANSFER DETAIL


BETWEEN FLOORS @ INTERIOR WALL

TYPICAL GABLE END DETAIL

STRAP SHALL BE FASTENED DIRECTLY TO HEADER OR TO FLAT 2x HEADER FULL DEPTH OF WALL @ BOTTOM OF STRUCTURAL HEADER <u>* * * ** * * * * * * */* * * *</u> HEAR WALL WITH EDGE NAILING & BLOCKING PER - SIMPSON CSI6 STRAP CENTERED AT CORNER OF OPENING w/ (26) 21/2"x 0.131" NAILS (28" MIN LENGTH) 4 HORIZONTAL BLOCKING DOOR FULL DEPTH OF WALL MAY BE INSTALLED FLAT IF STRAP IS ON EXTERIOR FACE OF WALL) - INSTALL 2 BAYS IF FIRST STUD IS LESS THAN 14" FROM

- STRAPS MAY BE INSTALLED ON EXTERIOR OR INTERIOR FACE OF WALL WHEN INSTALLED ON THE EXTERIOR FACE OF THE WALL STRAPS TO BE METALLED ON EXTERIOR FACE OF SHTG. & MAY BE MOVED 1½" FROM EDGE TO ALLOW FOR DOOR NAILING REQUIRED ONLY @ OPENINGS WHERE SPECIFIED ON PLAN

TYPICAL EXT. WALL & INT. 2 SHEARWALL OPENING ELEVATION



3 EXTERIOR SHEARWALL ABOVE

LATERAL/WALL BRACING & WALL SHEATHING SPECIFICATIONS

THIS MODEL HAS BEEN DESIGNED TO RESIST LATERAL FORCES RESULTING FROM:

15 MPH WIND IN 2018 IRC MAP

WIND MAP, PER IRC R301.2.1.1) EXP. B, RISK CAT. 2 & SEISMIC CAT. A/B.

THE DESIGN WAS COMPLETED PER 2018 IBC (SECTION 1609) & ASCE 7-16. AS PERMITTED BY R301.1.3 OF THE 2018 IRC, OR THE SIMPLIFIED PRESCRIPTIVE PROCEDURE IN ACCORDANCE WITH THE 2018 IRC IF THE PARAMETERS OF SECTION R602.12 COMPLY. ACCORDINGLY, THIS MODEL, AS DOCUMENTED AND DETAILED HEREWITHIN, IS ADEQUATE TO RESIST THE CODE REQUIRED LATERAL FORCES.

EXT. WALL SHEATHING SPECIFICATION

- 1/16" OSB OR 15/32" PLYWOOD: FASTEN SHEATHING W/ 2 3 × 0.113 NAILS @ 6" O.C. AT EDGES & @ 12" O.C. IN PANEL FIELD. (TYP, U.N.O.)
- HORIZONTAL BLOCKING OF EXT. WALL/SHEAR WALL
- ALL EXT. WALLS SHALL BE CONTINUOUSLY SHEATHED AND ARE CONSIDERED SHEAR WALLS.
- ALT. STAPLE CONNECTION SPEC: 1 3/4" 16 GA STAPLES (1/6" CROWN) @ 3" O.C. AT EDGES & @ 6" O.C IN FIELD.

3" O.C. EDGE NAILING

• AT DESIGNATED AREAS - FASTEN PANEL EDGES OF WOOD STRUCTURAL WALL SHEATHING TO FRAMING W 2 3" x 0.113" NAILS @ 3" O.C. AND 12" O.C. IN THE PANEL FIELD NO STAPLE ALTERNATIVE AVAILABLE AT THIS SPEC. ALL SHEATHING PANELS SHALL BE ORIENTED VERTICALLY (LONG DIRECTION PARALLEL TO STUD) AND INSTALLED FULL HEIGHT OF SHEAR WALL - OR - 2x HORIZONTAL BLOCKING SHALL BE PROVIDED TO SUPPORT UNSUPPORTED PANEL EDGES AND 3" O.C. EDGE FASTENING.

- STANDARD SHEAR TRANSFER DETAILING IF ADDITIONAL CAPACITY IS REQUIRED BY DESIGN, IT WILL BE SPECIFICALLY NOTED ON PLAN.
- DESIGN ASSUMES 16" O.C MAX. STUD SPACING, U.N.O.
- ALL STRUCTURAL PANELS ARE TO BE DIRECTLY APPLIED TO STUD FRAMING.
- FASTEN TOGETHER END STUDS OF WALL PANELS SHEATHED W/ OSB OR PLYWOOD W/ 3" x 0.120" NAILS @ 4" O.C. (THRU ONE SIDE ONLY)

SHEARWALL, BLOCKED PANEL EDGES, AND/OR 3" O.C. EDGE NAILING

INDICATES HOLDOWN

APPROVED

Montgomery County

Historic Preservation Commiss

Kare Bulit

CONNECTION SPECIFICATIONS (TYP. U.N.O.)

By Laura DiPasquale at 9:42 am, Jan 14, 2025

REVIEWED

| DESCRIPTION OF BLDG. ELEMENT | 3"x0.131" NAIL5 | 3"x0.120" NAILS |
|--------------------------------|--------------------------|---------------------------|
| JOIST TO SOLE PLATE | (3) TOENAILS | (3) TOENAILS* |
| SOLE PLATE TO JOIST/BLK'G. | (3) NAILS @ 4" o.c. | (3) NAILS @ 4" o.c. |
| STUD TO SOLE PLATE | (2) TOENAILS | (3) TOENAILS* |
| TOP OR SOLE PLATE TO STUD | (2) NAILS | (3) NAILS |
| RIM TO TOP PLATE | TOENAILS ● 8" o.c. | TOENAILS @ 6" o.c.* |
| BLK'G. BTWN. JOISTS TO TOP PL. | (3) TOENAILS | (3) TOENAILS* |
| DOUBLE STUD | NAILS ⊘ 24" o.c. | NAILS ⊘ 16" o.c. |
| DOUBLE TOP PLATE | NAIL5 @ 24" o.c. | NAILS @ 16" o.c. |
| DOUBLE TOP PLATE LAP SPLICE | (4) NAILS IN LAPPED AREA | (II) NAILS IN LAPPED AREA |
| TOP PLATE LAP @ CORNERS \$ | (2) NAIL5 | (2) NAIL5 |
| INTERSECTING WALLS | | |

2½"x0.113 IS AN ACCEPTABLE ALTERNATIVE TO A 3"x0.120", SAME SPACING OR NUMBER OF NAILS. (ONLY ACCEPTABLE WHERE * ARE SHOWN)

LETTERED DETAILS ARE TYPICAL FOR NUMBERED DETAILS ARE PLAN THIS HOME & SHALL BE IMPLEMENTED IN SPECIFIC AND ARE ONLY REQUIRED WHERE SPECIFICALLY INDICATED ALL APPLICABLE AREAS. THESE DETAILS ARE NOT "CUT" ON THE PLANS ("CUT") ON THE PLANS.

11/20/24

STRUCTURAL ENGINEER

CHINE S

Σä

Y

Irawn by:

REVISIONS:

JTR

TEV

initial:

ssue date: 10-24-24

(115 MPH WIND SPEED IN ASCE 7-16


- PANEL EDGES IS <u>NOT</u> REQUIRED BY THIS DESIGN EXCEPT FOR THOSE AREAS SPECIFICALLY NOTED.


093-240


- SEE CONNECTION SPECIFICATIONS CHART FOR
- PRE-MANUFACTURED PANELIZED WALLS:


INDICATES EXTENT OF INT. OSB


ER RAN











date:



9820

WSSC GRID 227NW15

TAX MAP DU562 **ELECTION DISTRICT - 11** M-NCPPC FILE NO. 42025066E

SHEET 1 OF 3

| | | SIGN | IFICANT / SP | ECIMEN TREE TAE | BLE | | |
|----------------|---------------------------|---------------------------|-----------------------------|------------------------------|--|---------------------|---------------------|
| TREE NUMBER | BOTANICAL NAME | COMMON NAME | SIZE (D.B.H.) | TREE CONDITION | COMMENTS | %OF CRZ IMPACTED | STATUS |
| ST-1 | Ailanthus altissima | Tree of Heaven | 15.0" & 15.0" (Estimate) | Moderate | | 0% | To Remain |
| ST-2* | llex opaca | American Holly | 30.1" | Moderate | Overhead utilities through canopy, off-site, adventitious | 0% | To Remain |
| ST-3 | Pinus strobus | White Pine | 16.7" | Moderate | limbs Lower broken & pruned limbs, low dead limbs | 0% | To Remain |
| ST-4 | Ailanthus altissima | Tree of Heaven | 18.1" | Moderate-Poor | Off-site | 0% | To Remain |
| ST-5 | Acer rubrum | Red Maple | 8.1" | Good-Moderate | Rope holding up fence, co-dominant leaders | 0% | To Remain |
| ST-6 ST-7 | Acer rubrum Pinus strobus | Red Maple White Pine | 6.7" 18.1" | Good-Moderate Moderate | Co-dominant leaders Phototopic lean | 0% 0% | To Remain To Remain |
| ST-8 | Carya glabra | Pignut Hickory | 18.0" (Estimate) | Moderate | Off-site, broken dead limbs, galls on trunk | 0% | To Remain |
| ST-9 | Picea rubens | Red Spruce | 10.0" (Estimate) | Good | Off-site | 0% | To Remain |
| ST-10 | Acer rubrum | Red Maple | 15.0" | 0.0 AC | Multi-stem, multiple vine species climbing trunk | 0% | To Remain |
| ST-11 | Juglans nigra | Black Walnut | 6.5" | Moderate | Broken limbs | 0% | To Remain |
| ST-12 | Prunus serotina | Black Cherry | 8.0" & 4.0" | Moderate | Off-site, not located, broken limbs | 0% | To Remain |
| ST-13 | Prunus serotina | Black Cherry | 8.0" (Estimate) & 3.0" | Moderate | Off-site, not located, phototropic lean | 0% | To Remain |
| ST-14 | Ailanthus altissima | Tree of Heaven | 24.0" (Estimate) | Moderate | Multiple vine species climbing trunk, adventitious limbs, broken dead limbs with decay, phototropic lean, co-dominant leaders | 20% | To Remain |
| ST-15* | Ailanthus altissima | Tree of Heaven | 36.0" (Estimate) | Poor | Off-site, not located, vine species climbing trunk, co-dominant leaders, broken dead limbs with decay, broken leaders | 25% | To Remain |
| ST-16 | Ailanthus altissima | Tree of Heaven | 7.0" | Moderate-Poor | Phototropic lean, hanger, broken dead limbs & leader with decay | 0% | To Remain |
| ST-17 | Ailanthus altissima | Tree of Heaven | 20.7" | Poor | Lost scaffold limb, sap sucker damage, broken dead limbs with | 25% | To Remain |
| ST-18 | Ailanthus altissima | Tree of Heaven | 26.6" | Poor | decay & leaders Possible basal rot, oozing sap, leaders have grown together, included wood, adventitious | 35% | To Remain |
| ST-19 | Ailanthus altissima | Tree of Heaven | 24.0" | Moderate | limbs, broken dead limbs & leader with decay With Poison Ivy, phototropic lean, adventitious limbs, unbalanced | 92% | To Be Removed |
| | | or rieaver | (Estimate) | model ale | canopy, broken dead limbs with decay | | |
| ST-20 | Acer negundo | Boxelder | 7.6" & 8.8" | Moderate-Poor | Canker with decay, basal rot, adventitious limbs Phototropic lean, multiple vine | 100% | To Be Removed |
| ST-21 | Ulmus pumila | Siberian Elm | 12.9" | Moderate | species climbing trunk, broken dead limbs with decay, enrolled wound, hanger | 26% | To Remain |
| ST-22 | Acer rubrum | Red Maple | 14.0" (Estimate) | Moderate-Poor | lean, adventitious limbs, lost scaffold limb now column of decay Not located, phototropic lean, | 15% | To Remain |
| ST-23 | Prunus serotina | Black Cherry | 18.8" | Poor | English Ivy climbing trunk, broken dead limbs with decay & leaders, partially failed limb Not located, adventitious limbs, | 34% | To Remain |
| ST-24 | Acer negundo | Boxelder | 12.4" | Moderate | phototropic lean, co-dominant leaders, broken dead limbs with decay | 19% | To Remain |
| ST-25 | Picea glauca | White Spruce | 8.0" (Estimate) | Moderate | Off-site, not located, sap sucker damage, phototropic lean | 0% | To Remain |
| ST-26 | Acer rubrum | Red Maple | 9.2" | Poor | Basal rot, sap sucker damage, co-dominant leaders, adventitious | 0% | To Remain |
| ST-27 | Ulmus pumila | Siberian Elm | 14.1" | Poor | limbs Off-site, not located, English Ivy climbing trunk, phototropic lean, wound oozing with decay, adventitious limbs, co-dominant | 0% | To Remain |
| ST-28 | Prunus serotina | Black Cherry | 9.0" (Estimate) | Poor | leaders Not located, across from Gazebo, phototropic lean, broken dead limbs with decay | 0% | To Remain |
| ST-29 | Robinian pseudoacacia | Black Locust | 18.0" | Moderate-Poor | Off-site, not located, adventitious limbs, conks on leader, broken | 1% | To Remain |
| ST-30 | Prunus serotina | Black Cherry | 8.0" (Estimate) | Moderate-Poor | dead limbs, co-dominant leaders Phototropic lean, adventitious | 0% | To Remain |
| | | | , | | limbs, co-dominant leaders Shared tree, not located, broken | | |
| ST-31 | Ulmus pumila | Siberian Elm | 24.0" (Estimate) & 11.2" | Moderate-Poor | dead limbs, sap rot, broken dead limbs with decay, co-dominant leaders | 3% | To Remain |
| ST-32 | Ulmus americana | American Sycamore | 6.1" | Good | Pruned, adventitious limbs, | 0% | To Remain |
| ST-33 | Prunus serotina | Black Cherry | 20.0" (Estimate) | Moderate-Poor | co-dominant leaders Off-site, not located, phototropic lean, multiple vine species in canopy, hangers, broken dead limbs with decay | 0% | To Remain |
| ST-34 | Ulmus pumila | Siberian Elm | 18.8" | Moderate-Poor | Exposed wounded girdling roots, phototropic lean, cavity oozing fluid, was multi-stem, included wood, broken dead leaders with | 0% | To Remain |
| ST-35 | Ailanthus altissima | Tree of Heaven | 24.0" (Estimato) | Moderate-Poor | decay, adventitious limbs Broken dead scaffold limb, broken dead limbs with decay, vine | 0% | To Remain |
| | | | (Estimate) | | species in canopy Multi-stem, probable basal rot, | | |
| ST-36 | Ulmus rubra | Slippery Elm | 6.0" | Moderate-Poor | broken dead limbs Multiple vine species climbing | 0% | To Remain |
| ST-37 | Ailanthus altissima | Tree of Heaven | 13.0" | Moderate-Poor | trunk, broken dead limbs with decay, lost one of co-dominant | 0% | To Remain |
| ST-38 | Ulmus rubra | Slippery Elm | 7.4" | Moderate-Poor | leaders Vine species climbing trunk, broken dead limbs with decay, | 0% | To Remain |
| ST-38 | Ulmus rubra | Slippery Elm Slippery Elm | 6.0" | Moderate-Poor Moderate-Poor | co-dominant leaders Phototropic lean, vine species climbing trunk, adventitious limbs, co-dominant leaders, broken | 0% | To Remain |
| ST-40 | Morus alba | White Mulberry | 8.3" | Moderate | leaders Phototropic lean, broken dead limbs with decay, co-dominant | 0% | To Remain |
| ST-41 | Prunus serotina | Black Cherry | 6.3" | Moderate-Poor | leaders Multiple vine species, climbing trunk, phototropic lean, broken | 0% | To Remain |
| U1-41 | i runus serulina | DIAGN CHELLY | 0.3 | ividuel ale-P00f | dead limbs with decay Was multi-stem, included wood, | U 70 | TO Remain |
| ST-42 | Morus alba | White Mulberry | 12.0" | Moderate-Poor | multiple vine species climbing trunk, tree was pruned, adventitious limbs, broken dead limbs with decay | 0% | To Remain |
| ST-43 | Ulmus americana | American Elm | 12.3" | Poor | Phototropic lean, basal rot, multiple vine species, adventitious limbs, broken dead limbs with decay | 0% | To Remain |
| ST-44 | Ulmus rubra | Slippery Elm | 7.7" | Poor | Multiple vine species climbing tree, adventitious limbs, phototropic lean, broken dead limbs | 0% | To Remain |
| ST-45 | Robinian pseudoacacia | Black Locust | 28.6" | Moderate | Multiple vine species climbing trunk, broken dead limbs, hangers, co-dominant leaders, adventitious limbs | 0% | To Remain |
| | Morus alba | White Mulberry | 6.7" | Moderate-Poor | Phototropic lean, broken dead limbs, co-dominant leaders, | 0% | To Remain |
| ST-46 | WOI US AIDA | | | | multiple vine species | | |
| ST-46 ST-47 | Prunus serotina | Black Cherry | 14.0" (Estimate) | Moderate-Poor | multiple vine species Multiple vine species on trunk, broken dead limbs with decay, co-dominant leaders | 0% | To Remain |

| TREE NUMBER | BOTANICAL NAME | COMMON NAME | SIZE (D.B.H.) | TREE CONDITION | COMMENTS | % OF CRZ IMPACTED | STATU |
|-------------|----------------------|-------------------|-----------------------------|----------------|--|----------------------|---------|
| ST-49 | Ulmus rubra | Slippery Elm | 10.0" (Estimate) | Poor | Multiple vine species, tree has been pruned, adventitious limbs, broken dead limbs with decay | 0% | To Rema |
| ST-50 | Prunus serotina | Black Cherry | 12.3" & 10.0" (Estimate) | Poor | Dead broken leader, dead broken limbs with decay, multiple vine species in canopy | 0% | To Rema |
| ST-51 | Morus alba | White Mulberry | 17.7" | Moderate-Poor | Phototropic lean, multiple vine species climbing trunk, tree has been pruned, co-dominant leaders, broken dead limbs with decay | 0% | To Rema |
| ST-52 | Ailanthus altissima | Tree of Heaven | 10.5" | Moderate-Poor | Possible basal rot, multiple vine species, phototropic lean, co-dominant leaders, broken dead limbs | 0% | To Rem |
| ST-53 | Ailanthus altissima | Tree of Heaven | 11.3" | Moderate-Poor | Possible basal rot, galls on trunk, co-dominant leaders, broken dead limbs | 0% | To Rema |
| ST-54 | Ailanthus altissima | Tree of Heaven | 11.9" | Moderate-Poor | Probable basal rot, vertical crack, broken dead limbs with decay, co-dominant leaders | 0% | To Rema |
| ST-55 | Ailanthus altissima | Tree of Heaven | 18.1" | Poor | Wire fence in trunk, several enrolled wounds with decay on trunk, galls, response wood growth below branch union, co-dominant leaders, broken dead limbs with decay | 0% | To Rem |
| ST-56 | Juglans nigra | Black Walnut | 17.3" | Moderate | Pruned, co-dominant leaders, hangers | 0% | To Rema |
| ST-57 | Prunus serotina | Black Cherry | 22.2" | Poor | Lost scaffold limb, cavity with decay, dead broken limbs, adventitious limbs, multiple vine species, large wound with decay on upper trunk, lost leader, dead leader | 0% | To Rema |
| ST-58 | Prunus serotina | Black Cherry | 17.0" | Poor | Probable basal rot, cavity with decay, multiple vine species climbing trunk, pruned, adventitious limbs, broken dead limbs with decay | 0% | To Rem |
| ST-59 | Morus alba | White Mulberry | 15.4" | Moderate-Poor | Phototropic lean, 15% visible girdling roots, broken dead limbs with decay, co-dominant leaders, pruned, vine species in canopy | 0% | To Rema |
| ST-60 | Ailanthus altissima | Tree of Heaven | 21.9" | Moderate | Basal rot, 15% visible girdling roots, vine species climbing trunk, co-dominant leaders | | To Rem |
| ST-61 | Fraxinus americana | White Ash | 14.7" | Poor | Pruned, broken dead limbs with decay, vine species in canopy, large wound on fence side of trunk, co-dominant leaders | 0% | To Rem |
| ST-62 | Prunus serotina | Black Cherry | 15.2" | Poor | Canker, basal rot, vine species climbing trunk, phototropic lean, lost scaffold limb, wound cavity with decay, broken dead limbs with decay, adventitious limbs, co-dominant leaders | 0% | To Rem |
| ST-63 | Prunus serotina | Black Cherry | 19.5" | Moderate | Vine species on trunk, phototropic lean, broken dead limbs with decay, adventitious limbs, co-dominant leaders | 0% | To Rem |
| ST-64 | Juglans nigra | Black Walnut | 18.6" | Moderate | Multiple vine species in canopy, broken dead limbs, co-dominant leaders | 0% | To Rem |
| ST-65 | Prunus serotina | Black Cherry | 16.7" | Poor | Canker with decay, basal rot, multiple vine species in canopy, broken dead limbs with decay, co-dominant leaders | 0% | To Rem |
| ST-66 | Prunus serotina | Black Cherry | 26.3" | Poor | Basal rot, phototropic lean, broken dead limbs with decay, multiple dead vines species in canopy, dead leader | 0% | To Rem |
| ST-67 | Ulmus americana | American Elm | 8.0" (Estimate) | Moderate | Off-site, not located, covered in vine species, co-dominant leaders, broken dead limbs with decay | 0% | To Rem |
| ST-68 | Fraxinus americana | White Ash | 14.0" (Estimate) | Moderate-Poor | Off-site, not located, broken dead limbs with decay, hangers, adventitious limbs, multiple partially failed limbs | 0% | To Rem |
| ST-69 | Juglans nigra | Black Walnut | 12.0" (Estimate) | Moderate | Off-site, not located, broken dead limbs with decay, co-dominant leaders | 0% | To Rem |
| ST-70 | Acer negundo | Boxelder | 14.0" & 12.0" (Estimate) | Moderate | Multi-stem, off-site, not located, broken dead limbs with decay, co-dominant leaders | 0% | To Rem |
| ST-71 | Juglans nigra | Black Walnut | 10.7" | Moderate | Not located, broken dead limbs with decay, co-dominant leaders | 0% | To Rem |
| ST-72 | Quercus coccinea | Scarlet Oak | 11.2" | Moderate | Broken dead limbs with decay, adventitious limbs, co-dominant leaders | 0% | To Rem |
| ST-73 | Ailanthus altissima | Tree of Heaven | 8.0" | Good | Broken dead limbs, co-dominant leader | 0% | To Rem |
| ST-74 | Juniperus virginiana | Eastern Red Cedar | 10.8" | Moderate | Tree pruned, dead vine species in canopy, co-dominant leaders Multi-stem, tree pruned, | 0% | To Rem |
| ST-75 | Juniperus virginiana | Eastern Red Cedar | 12.9" | Moderate | co-dominant leaders, dead vines in canopy | 0% | To Rema |
| ST-76 | Juniperus virginiana | Eastern Red Cedar | 15.6" | Moderate | Pruned, co-dominant leaders, dead lower limbs | 0% | To Rem |
| ST-77 | Juniperus virginiana | Eastern Red Cedar | 6.3" | Moderate | | 0% | To Rem |
| ST-78 | Morus alba | White Mulberry | 9.5" | Moderate | Dead broken lower limbs, co-dominant leaders | 0% | To Rem |
| ST-79 | Acer rubrum | Red Maple | 9.0" | Moderate | Phototropic lean, dead broken limbs, co-dominant leaders | 0% | To Rem |
| ST-80 | Pinus strobus | White Pine | 7.6" | Moderate | | 0% | To Rem |
| ST-81 | Quercus palustris | Pin Oak | 11.9" | Good-Moderate | Dead broken lower limbs, Grapevine in canopy, | 0% | To Rem |
| ST-82 | Pinus strobus | White Pine | 10.7" | Moderate | co-dominant leaders Multi-stem, pruned, oozing sap, Grapevine | 0% | To Rema |
| ST-83 | Juniperus virginiana | Eastern Red Cedar | 6.7" | Moderate | ' | 0% | To Rema |
| ST-84* | Morus alba | White Mulberry | 38.0" (Estimate) | Poor | Pruned, broken dead limbs, | 49% | To Rema |
| ST-85 | Juniperus virginiana | Eastern Red Cedar | (Estimate) | Moderate | co-dominant leaders Canker with decay, broken lower limbs | 80% | To Rem |
| ST-86 | Ailanthus altissima | Tree of Heaven | 10.0" & 8.0" (Estimate) | Moderate | | 48% | To Rem |
| ST-87 | Ailanthus altissima | Tree of Heaven | 8.0" (Estimate) | Moderate | Dead broken limbs | 44% | To Rema |
| ST-88 | Ailanthus altissima | Tree of Heaven | 7.0" (Estimate) | Moderate | Broken limbs | 10% | To Rema |
| ST-89 | Ailanthus altissima | Tree of Heaven | 14.0" & 18.0" Estimate | Moderate | | 4% | To Rema |

*SPECIMEN TREE

12/10/2024 date:



19820 White Ground Road
Election District 11
Parcel 404; Tax Map DU562
Montgomery County, Maryland

Montgomery County Historic Preservation Commission

APPROVED

By Laura DiPasquale at 10:08 am, Jan 14, 2025

REVIEWED



Professional Certification:
I hereby certify that this plan was prepared by me or under my direct supervision and that I am a duly licensed landscape architect registered to practice in the State of Maryland.

12-10-2024 10-21-2026

Signature Date Exp. Date

Exp. Date Date

WSSC GRID 227NW15 TAX MAP DU562 ELECTION DISTRICT - 11 M-NCPPC FILE NO. 42025066E

SHEET 2 OF 3

*SPECIMEN TREE

The property owner is responsible for ensuring all tree protection measures are performed in accordance with the approved final forest conservation plan or tree save plan, and as modified in the field by a Planning Department Forest Conservation Inspector. The measures must meet or exceed the most recent standards published by the American National Standards Institute (ANSI

Pre-Construction

- 1. An on-site pre-construction meeting is required after the limits of disturbance have been staked and flagged and before any land disturbance.
- 2. The property owner must arrange for the meeting and following people should must participate at the pre-construction meeting: the property owner or their representative, construction superintendent, International Society of Arboriculture (ISA) certified arborist/Maryland Licensed Tree Expert (representing owner) that will implement the tree protection measures, The Planning Department Forest Conservation Inspector, and Montgomery County Department of Permitting Services (DPS) Sediment Control Inspector. The purpose of this meeting is verify the limits of disturbance and discuss specific tree protection and tree care measures shown on the approved plan. No land disturbance shall begin before tree protection and stress-reduction measures have been
- implemented and approved by the Planning Department's Forest Conservation Inspector. Typical tree protection devices include:
 - i. Chain link fence (four feet high) ii. Super silt fence with wire strung between the support poles (minimum 4
- feet high) with high visibility flagging. iii. 14 gauge, 2 inch x 4 inch welded wire fencing supported by steel T-bar posts (minimum 4 feet high) with high visibility flagging.
- b. Typical stress reduction measures may include, but are not limited to: i. Root pruning with a root cutter or vibratory plow designed for that
- purpose. Trenchers are not allowed, unless approved by the Forest Conservation Inspector
- ii. Crown Reduction or pruning iii. Watering
- iv. Fertilizing
- v. Vertical mulching vi. Root aeration systems

Measures not specified on the Forest Conservation Plan may be required as determined by the Forest Conservation Inspector in coordination with the property owner's arborist.

3. A Maryland Licensed Tree expert must perform, or directly supervise, the implementation of all stress reduction measures. Documentation of the process (including

photographs) may be required by the Forest Conservation Inspector, and will be

4. Temporary tree protection devices must be installed per the approved Forest Conservation Plan, Exemption Plan, or Tree Save Plan and prior to any land disturbance. The Forest Conservation Inspector, in coordination with the DPS Sediment Control Inspector, may make field adjustments to increase the survivability of trees and forest shown as saved on the approved plan.

- 5. Tree protection fencing must be installed and maintained by the property owner for the duration of construction project and must not be altered without prior approval from the Forest Conservation Inspector. All construction activity within protected tree and forest areas is prohibited. This includes the following activities:
- a. Parking or driving of equipment, machinery or vehicles of any type.
- b. Storage of any construction materials, equipment, stockpiling, fill, debris, etc. c. Dumping of any chemicals (i.e., paint thinner), mortar or concrete remainder,
- trash, garbage, or debris of any kind. d. Felling of trees into a protected area.
- e. Trenching or grading for utilities, irrigation, drainage, etc.
- 6. Forest and tree protection signs must be installed as required by the Forest Conservation Inspector. The signs must be waterproof and wording provided in both English and

During Construction

- 7. Periodic inspections will be made by the Forest Conservation Inspector. Corrections and repairs to tree protection devices must be completed within the timeframe given by the
- 8. The property owner must immediately notify the Forest Conservation Inspector of any damage to trees, forests, understory, ground cover, and any other undisturbed areas shown on the approved plan. Remedial actions, and the relative timeframes to restore these areas, will be determined by the Forest Conservation Inspector.

Post-Construction

9. After construction is completed, but before tree protection devices have been removed, the property owner must request a final inspection with the Forest Conservation Inspector. At the final inspection, the Forest Conservation Inspector may require

February 2017

- additional corrective measures, which may include: a. Removal, and possible replacement, of dead, dying, or hazardous trees b. Pruning of dead or declining limbs
- c. Soil aeration d. Fertilization
- e. Watering
- f. Wound repair

Page 2 of 3

g. Clean up of retention areas, including trash removal

10. After the final inspection and completion of all corrective measures the Forest Conservation Inspector will request all temporary tree and forest protection devices be removed from the site. Removal of tree protection devices that also operate for erosion and sediment control must be coordinated with both DPS and the Forest Conservation Inspector and cannot be removed without permission of the Forest Conservation Inspector. No additional grading, sodding, or burial may take place after the tree protection fencing is removed.

11. Long-term protection measures, including permanent signage, must be installed per the approved plan. Installation will occur at the appropriate time during the construction project. Refer to the approved plan drawing for the long-term protection measures to be

INSPECTIONS

All field inspections must be requested by the applicant.

Field Inspections must be conducted as follows:

Plans without Planting Requirements


- 1. After the limits of disturbance have been staked and flagged, but before any clearing or
- grading begins.


 2. After necessary stress reduction measures have been completed and protection measures
- have been installed, but before any clearing and grading begin and before release of the
- 3. After completion of all construction activities, but before removal of tree protection fencing, to determine the level of compliance with the provision of the forest

Additional Requirements for Plans with Planting Requirements

- 4. Before the start of any required reforestation and afforestation planting.
- 5. After the required reforestation and afforestation planting has been completed to verify that the planting is acceptable and prior to the start the maintenance period.
- 6. 2 years after reforestation and afforestation have been completed, to determine survival and assess necessary maintenance activities for the remaining duration of the maintenance and management period.
- 7. At the end of the maintenance period to determine the level of compliance with the provisions of the planting plan, and if appropriate, release of the performance bond.

CONSTRUCTION SIGNS






SOIL IMPROVEMENT DETAIL - TREES PLANTED IN NON RESTRICTED SOIL CONDITIONS


 \prime note: this detail assumes that the area of loamy soil available to each tree is a minimum of


45 SQ. M (500 SQ. FT)



- 1. RETENTION AREAS WILL BE SET AS PART OF THE REVIEW PROCESS AND
- PRECONSTRUCTION MEETING. 2. BOUNDARIES OF RETENTION AREAS MUST BE STAKED AT THE PRECONSTRUCTION
- MEETING AND FLAGGED PRIOR TO TRENCHING. 3. EXACT LOCATION OF TRENCH SHALL BE DETERMINED IN THE FIELD IN COORDINATION WITH THE FOREST CONSERVATION (FC) INSPECTOR.
- 4. TRENCH SHOULD BE IMMEDIATELY BACKFILLED WITH EXCAVATED SOIL OR OTHER DRGANIC SDIL AS SPECIFIED PER PLAN DR BY THE FC INSPECTOR.
- 5. RODTS SHALL BE CLEANLY CUT USING VIBRATORY KNIFE OR OTHER ACCEPTABLE
- 6. ALL PRUNING MUST BE EXECUTED WITH LOD SHOWN ON PLANS OR AS AUTHORIZED IN WRITING BY THE FC INSPECTOR.


PRUNING DETAIL NOT TO SCALE






Montgomery County Planning Department • 🥞 M-NCPPC

MontgomeryPlanning.org




THE MARYLAND-NATIONAL CAPITAL PARK AND PLANNING COMMISSION



| TREE PLANTING SCHEDULE | | | | | | | |
|------------------------|---------|----------------|----------------|------------------|----------|--|--|
| QUANTITY | TREE ID | BOTANICAL NAME | COMMON NAME | SIZE (D.B.H.) | COMMENTS | | |
| 2 | QA | Quercus alba | White Oak | 3" | B&B | | |





APPROVED





Professional Certification: I hereby certify that this plan was prepared by me or under my direct supervision and that I am a duly licensed landscape architect registered to practice in the State of Maryland.

Signature

12-10-2024 10-21-2026 Exp. Date Date

WSSC GRID 227NW15 TAX MAP DU562 **ELECTION DISTRICT - 11** M-NCPPC FILE NO. 42025066E

SHEET 3 OF 3

Revisions

ale date

ound Road ict 11 ap DU562

U562 ryland TREE SAMPITE

White
Election 20 Δ ≥

0



