

#### HISTORIC PRESERVATION COMMISSION

Marc Elrich
County Executive
Chair

Date: 7/24/2025

#### **MEMORANDUM**

TO: Rabbiah Sabbakhan

Department of Permitting Services

FROM: Laura DiPasquale

**Historic Preservation Section** 

Maryland-National Capital Park & Planning Commission

SUBJECT: Historic Area Work Permit #1121920– Solar panel installation

The Montgomery County Historic Preservation Commission (HPC) has reviewed the attached applications for a Historic Area Work Permit (HAWP). This application was **approved** at the July 23, 2025 HPC meeting.

The HPC staff has reviewed and stamped the attached submission materials.

THE BUILDING PERMIT FOR THIS PROJECT SHALL BE ISSUED CONDITIONAL UPON ADHERENCE TO THE ABOVE APPROVED HAWP CONDITIONS AND MAY REQUIRE APPROVAL BY DPS OR ANOTHER LOCAL OFFICE BEFORE WORK CAN BEGIN.

Applicant: Brian Levy; Tina Crouse (Agent) Address: 7129 Maple Avenue, Takoma Park

This HAWP approval is subject to the general condition that the applicant will obtain all other applicable Montgomery County or local government agency permits. After the issuance of these permits, the applicant must contact this Historic Preservation Office if any changes to the approved plan are made. Once work is complete, the applicant will contact Laura DiPasquale at 301-495-2167 or <a href="mailto:laura.dipasquale@montgomeryplanning.org">laura.dipasquale@montgomeryplanning.org</a> to schedule a follow-up site visit.





# **APPLICATION FOR** HISTORIC AREA WORK PERMIT HISTORIC PRESERVATION COMMISSION 301.563.3400

HAWP#\_ DATE ASSIGNED\_\_\_\_

FOR STAFF ONLY:

AFF LIVANII.	
Name: Brian Levy	E-mail: levybd@gmail.com
Address: 7129 Maple Avenue	city: Takoma Park zip: 21042
Daytime Phone: 202-247-5106	Tax Account No.: 13-01076642
AGENT/CONTACT (if applicable):	
Name: Tina Crouse	E-mail: tcrouse@solarenergyworld.com
Address: 14880 Sweitzer Lane	city: Laurel zip: 20707
Daytime Phone: 410-570-4157	Contractor Registration No.: 127353
LOCATION OF BUILDING/PREMISE: MIHP # of	Historic Property
map of the easement, and documentation from the standard of the Planning and/or Hearing Examiner App (Conditional Use, Variance, Record Plat, etc.?) If Supplemental information.	No/Individual Site Nameironmental Easement on the Property? If YES, include a the Easement Holder supporting this application.  provals / Reviews Required as part of this Application? YES, include information on these reviews as
	Maple Avenue
Town/City: Takoma Park Neare	st Cross Street: Tulip Avenue
Lot: 8 Block: 3 Subdiv	rision: 0025 Parcel: 0000
for proposed work are submitted with this a be accepted for review. Check all that apply:  New Construction  Deck/Porch  Addition  Fence  Demolition  Grading/Excavation  I hereby certify that I have the authority to make	Shed/Garage/Accessory Structure
	his to be a condition for the issuance of this permit.

Description of Property: Please describe the building and surrounding environment. Include information on significant structures, landscape features, or other significant features of the property:

Property Built in 1936

Description of Work Proposed: Please give an overview of the work to be undertaken:

- -Install (28) roof mounted solar panels on detached structure
- -Micro Inverters to be placed under each panel
- -Utility disconnect to be installed next to utility meter along with electrical combiner box for micro inverters

Galvanized steel conduit to run from equipment to main house along side the Utility Meter to the array.

REVIEWED

By Laura DIPasquale at 2:19 pm, Jul 24, 2025

**APPROVED** 

**Montgomery County** 

**Historic Preservation Commission** 



Front of Home



Back of Home

## **REVIEWED**

By Laura DIPasquale at 2:19 pm, Jul 24, 2025

#### APPROVED

Montgomery County

Historic Preservation Commission



Left side Home



Right side of Home

## **REVIEWED**

By Laura DIPasquale at 2:19 pm, Jul 24, 2025

APPROVED

Montgomery County

Historic Preservation Commission



Utility Meter before Install

## **REVIEWED**

By Laura DIPasquale at 2:19 pm, Jul 24, 2025

#### APPROVED

**Montgomery County** 

**Historic Preservation Commission** 



Utility Meter after Install. To run along side the meter/conduit and along the roof ridge to the Array.

## APPROVED

Montgomery County


**Historic Preservation Commission** 

Kam Bulit

**REVIEWED** 

By Laura DIPasquale at 2:19 pm, Jul 24, 2025







**EY** FIRE SAFETY ZONE



3' PATHWAYS FROM LOWEST ROOF EDGE TO RIDGE PROVIDED PER R324.6.1



3' PATHWAYS PROVIDED ON BOTH SIDES OF RIDGE PER R324.6.2

PLAN VIEW TOTAL ROOF AREA: 1334 SQFT

SOLAR ARRAY AREA: 589.40 SQFT

THE SOLAR ARRAY IS 44.2% OF THE PLAN VIEW TOTAL ROOF AREA

#### NOTES:

- 1. THE SYSTEM SHALL INCLUDE (28) MSE410HT0B.
- 2. SNAPNRACK TOPSPEED WILL BE INSTALLED IN ACCORDANCE WITH SNAPNRACK INSTALLATION MANUAL

3. REFER TO STRUCTURAL DRAWING FOR SECTIONS MARKED AND ADDITIONAL NOTES.

**REVIEWED** 

By Laura DIPasquale at 2:20 pm, Jul 24, 2025



SOLAR PANEL LAYOUT

Scale: 1/8" = 1'-0"





Solar Energy World LLC. 14880 Sweitzer Lane Laurel, MD 20707 (888) 497-3233

Disclain

This drawing is the property of Solar Energy World Inc. The information herein contained shall be used for the sole benefit of Solar Energy World. It shall not be disclosed to others outside the recipient's organization, in whole or in part, without the written permission of Solar Energy World, except in connection with the sale and use of the respective Solar Energy equipment.

uniternational Residential Code (IRC) 2021

National Electrical Code (NEC) 2023

115 MPH

(28) MSE410HT0B

30 PSF

verter(s)

(28) IQ8+-72-M-US

DC System Size

11.480 kW 8.120 kW

Brian Levy 7129 Maple Ave Takoma Park, MD 20912

Partner/Lender
None

ANJ
Montgomery County


Sheet Name

Solar Panel Layout

Date
Date
AMP

June 9, 2025

AS NOTED MD25215 A-1







Solar Energy World LLC. 14880 Sweitzer Lane Laurel, MD 20707 (888) 497-3233

International Residential Code (IRC) 2021

National Electrical Code (NEC) 2023

30 PSF 115 MPH

(28) MSE410HT0B

(28) IQ8+-72-M-US

8.120 kW 11.480 kW

Customer Information
Brian Levy
7129 Maple Ave Takoma Park, MD 20912

None None

Montgomery County

Site Plan


AMP

June 9, 2025

Pepco DC

AS NOTED MD25215





APPROVED

**Montgomery County Historic Preservation Commission** 

Kare Bulit

**EQUIPMENT LOCATION PLAN** 

**REVIEWED** 

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

**SolarEnergyWorld Because Tomorrow Matters** 

Solar Energy World LLC. 14880 Sweitzer Lane Laurel, MD 20707 (888) 497-3233

This drawing is the property of Solar Energy World Inc. The information herein contained shall be used for the sole benefit of Solar Energy World. It shall not be disclosed to others outside the recipient's organization, in whole or in part, without the written permission of Solar Energy World, except in connection with the sale and use of the respective Solar Energy equipment.

International Residential Code (IRC) 2021

National Electrical Code (NEC) 2023

115 MPH

30 PSF

(28) IQ8+-72-M-US

(28) MSE410HT0B

8.120 kW 11.480 kW

Brian Levy 7129 Maple Ave Takoma Park, MD 20912

None


Montgomery County

Pepco DC

Equipment Location Plan

AMP June 9, 2025

E-1 AS NOTED MD25215



## **REVIEWED**

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

MODULE SPECIFICATIONS							
MODEL NUMBER	MSE410HT0B						
PEAK POWER			410 W				
RATED VOLTAGE (Vmpp)			31.38 V				
RATED CURRENT (Imp)			13.07 A				
OPEN CIRCUIT VOLTAGE (Voc)			37.41 V				
SHORT CIRCUIT CURRENT (Isc)			13.90 A				
MAXIMUM SYSTEM VOLTAGE			1000VDC				
INVERTER SPECIFICATIONS							
MODEL NUMBER	IQ8PLUS-72-M-US						
MAXIMUM DC VOLTAGE			60 V				
MAXIMUM POWER OUTPUT			290 W				
NOMINAL AC VOLTAGE			240 VAC				
MAXIMUM AC CURRENT			1.21 A				
CEC EFFICIENCY	97.0%						
ARRAY	<b>DETAIL</b>	S					
NO. OF MODULES PER STRING	10	9	9				
NO. OF STRINGS	1 1						
ARRAY WATTS AT STC	4100	3690	3690				

#### 3-LINE DIAGRAM

APPROVED

Montgomery County

**Historic Preservation Commission** 

Kare Bulit

Г	WIRE/CONDUIT SCHEDULE ARRAY					
T,	٩G	DESCRIPTION	WIRE SIZE/TYPE	NOTES		
	1	Panel to Micro Inverter	PV Wire (Factory Made)	INTEGRATED		
Г	2	Micro Inverter to Micro Inverter	Pre-Manufactured Cable			
Г	3	Micro Inverter to Transition Box	Pre-Manufactured Cable			
Г	ЗА	Transition Box to Load Center	#10 THHN/THWN-2	INTEGRATED		
Г	4	Load Center to AC Disconnect	#8 Cu THHN/THWN-2			
Г	5	AC Disconnect to AC Disconnect	#8 Cu THHN/THWN-2			
Г	6	AC Disconnect to Interconnection Point	#6 Cu THHN/THWN-2			
Г	7	Equipment Grounding Conductor	#8 Cu Bare Copper Wire			
Г	8	Equipment Grounding Conductor	#8 Cu THHN/THWN-2			
Г	9	Grounding Electrode Conductor	#6 Cu			

#### GENERAL ELECTRIC NOTES: NEC2023

- EQUIPMENT USED SHALL BE NEW, UNLESS OTHERWISE NOTED.
  EQUIPMENT USED SHALL BE UL LISTED, UNLESS OTHERWISE NOTED.
- 3. EQUIPMENT SHALL BE INSTALLED PROVIDING ADEQUATE PHYSICAL WORKING SPACE AROUND THE EQUIPMENT AND SHALL COMPLY WITH NEC.
- COPPER CONDUCTORS SHALL BE USED AND SHALL HAVE AN INSULATION RATING OF 600V, 90°C, UNLESS OTHERWISE NOTED
- CONDUCTORS SHALL BE SIZED IN ACCORDANCE TO THE NEC. CONDUCTORS AMPACITY SHALL BE DE-RATED FOR TEMPERATURE INCREASE, CONDUIT FILL AND VOLTAGE DROP.
- ALL CONDUCTORS, EXCEPT PV WIRE SHALL BE INSTALLED IN APPROVED CONDUITS OR RACEWAY. CONDUITS SHALL BE ADEQUATELY SUPPORTED AS PER NEC
- AC DISCONNECT SHOWN IS REQUIRED IF THE UTILITY REQUIRES VISIBLE-BLADE SWITCH.
- EXPOSED NON-CURRENT CARRYING METAL PARTS SHALL BE GROUNDED AS PER NEC.
- LINE SIDE INTER-CONNECTION SHALL COMPLY WITH NEC.
- SMS MONITORING SYSTEM AND IT'S CONNECTION SHOWN IS OPTIONAL. IF USED, REFER TO SMS INSTALLATION MANUAL FOR WIRING METHODS AND OPERATION PROCEDURE.
- 11. ASHRAE FUNDAMENTAL OUTDOOR DESIGN TEMPERATURES DO NOT EXCEED 47°C IN THE U.S.
- (PHOENIX, AZ OR PALM SPRINGS, CA)

  12. FOR LESS THAN 9 CURRENT-CARRYING CONDUCTORS IN ROOF MOUNTED SUNLIGHT CONDUIT USING THE OUTDOOR TEMPERATURE OF 47°C
- 12.1. 10AWG CONDUCTOR ARE GENERALLY ACCEPTABLE FOR MODULES WITH AN Isc OF 9.6 AMPS WIRE SIZING FOR OCPD

EX (Isc \*(1.25)(1.25)(# OF STRINGS IN PARALLEL) = WIRE AMPACITY OR USING NEC TABLE 690.8



Solar Energy World LLC. 14880 Sweitzer Lane Laurel, MD 20707

This drawing is the property of Solar Energy World Inc. The information herein contained shall be used for the sole benefit of Solar Energy World. It shall not be disclosed to others outside the recipients organization, in whole or in part, without the written permission of Solar Energy World, except in connection with the sole and use of the respective Solar Energy equipment.

International Residential Code (IRC) 2021

National Electrical Code (NEC) 2023

115 MPH 30 PSF

(28) MSE410HT0B

(28) IQ8+-72-M-US

11.480 kW 8.120 kW

**Brian Levy** 

7129 Maple Ave Takoma Park, MD 20912

None Pepco DC Montgomery County Electrical 3-Line Diagram

AMP June 9, 2025

AS NOTED MD25215

E-2





Solar Energy World LLC. 14880 Sweitzer Lane Laurel, MD 20707

This drawing is the property of Solar Energy World Inc. The information herein contained shall be used for the sole benefit of Solar Energy World. It shall not be disclosed to others outside the recipients organization, in whole or in part, without the written permission of Solar Energy World, except in connection with the sole and use of the respective Solar Energy equipment.

International Residential Code (IRC) 2021

National Electrical Code (NEC) 2023

30 PSF 115 MPH

(28) MSE410HT0B

(28) IQ8+-72-M-US

8.120 kW 11.480 kW

Brian Levy

7129 Maple Ave Takoma Park, MD 20912

None

Montgomery County


Pepco DC


Structural Attachment Details

AMP

AS NOTED MD25215


June 9, 2025 S-1





#### NOTES:

- 1. ALL WORK SHALL COMPLY WITH REQUIREMENTS OF INTERNATIONAL RESIDENTIAL CODE (IRC 2021), LOADING CODE (ASCE 7-16), WOOD DESIGN CODE (NDS 2015), AND LOCAL REQUIREMENTS.
- 2. LOAD CRITERIA PER
  - EXPOSURE CATEGORY "B"
  - GROUND SNOW LOAD, Pg = 30 PSF
  - LATERAL LOAD RISK CATEGORY "II"
  - ULTIMATE DESIGN WIND SPEED = 115 MPH
- 3. SOLAR PANELS AND RACKING SYSTEMS SHALL BE INSTALLED PER MANUFACTURER'S RECOMMENDATION.
- 4. FOLLOW ALL LOCAL AND FEDERAL SAFETY REQUIREMENTS.



## **REVIEWED**

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

APPROVED

**Montgomery County** 


**Historic Preservation Commission** 


Kare Bulit

STRUCTURAL ATTACHMENT DETAIL

Bill Of Materials					
Product	Count				
Mounts Without Spacers	56				
Mounts With Spacers	26				
Clamps Without Spacers	0				
Clamps With Spacers	10				







#### SOLAR PANEL FOOTING PLAN R2 Scale: 3/16" = 1'-0"

**ROOF RIDGE** 

SOLAR PANEL FOOTING PLAN R3

Scale: 3/16" = 1'-0"

#### NOTES:

KEY

MOUNTS WITHOUT SPACERS

CLAMPS WITHOUT SPACERS

MOUNTS WITH SPACERS

CLAMPS WITH SPACERS

- 1. SNAPNRACK TOPSPEED SHALL BE INSTALLED IN ACCORDANCE WITH SNAPNRACK INSTALLATION MANUAL.
- 2. ADD TOPSPEED CLAMP IF GREATER THAN (SOLAR PANEL LENGTH / 4) FOR LANDSCAPE OR (SOLAR PANEL WIDTH /4) FOR PORTRAIT
- 3. NO SOLAR PANEL SHALL CANTILEVER MORE THAN 1/4 SOLAR PANEL LENGTH OR WIDTH DEPENDING ON ORIENTATION. UNLESS FOR MANUFACTURER SPECIFIED CLAMPING ZONE

## **REVIEWED**

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

## APPROVED **Montgomery County Historic Preservation Commission**

# SolarEnergyWorld Because Tomorrow Matters

Solar Energy World LLC. 14880 Sweitzer Lane Laurel, MD 20707

This drawing is the property of Solar Energy World Inc. The information herein contained shall be used for the sole benefit of Solar Energy World. It shall not be disclosed to others outside the recipients organization, in whole or in part, without the written permission of Solar Energy World, except in connection with the sole and use of the respective Solar Energy equipment.

International Residential Code (IRC) 2021

National Electrical Code (NEC) 2023

115 MPH 30 PSF

(28) MSE410HT0B

(28) IQ8+-72-M-US

8.120 kW 11.480 kW

Brian Levy 7129 Maple Ave Takoma Park, MD 20912

(None					
Montgomery County		Pepco DC			
Solar F	Panel	Footing	Plan		
AMP Date June 9, 2025					
AS NOTED	MD2	25215	S-2		



## DAVID C. HERNANDEZ, PE

513-418-8812

4912 Prospect Ave., Blue Ash OH 45242



davehernandezpe@gmail.com



DATE: June 9, 2025

RE: 7129 Maple Ave, Takoma Park, MD 20912, USA

To Whom It May Concern,

As per your request, Exactus Energy has conducted a site assessment of the building at the above address.

PV solar panels are proposed to be installed on roof areas as shown in the submitted plans. The panels are clamped and attached to the roof decking with a rail-less mounting system. The PV system (PV modules, racking, mounting hardware, etc.) shall be installed according to the manufacturer's approved installation specifications. The Engineer of Record and Exactus Energy claim no responsibility for misuse or improper installation.

It was found that the roof structures satisfactorily meet the applicable standards included in the 2021 IBC/IRC and ASCE 7-16 as well as the design criteria shown below:

#### Design Criteria:

Risk Category = ||**Exposure Category** = B


Wind speed = 115 mph Ground snow load = 30 psfRoof dead load = 12 psf Solar system dead load = 3 psf

Overall, the roof area is structurally adequate to support the PV alteration with no modifications or reinforcements required.

This letter was completed in accordance to recognized design standards, professional engineering experience, and judgement. Prior to installation, the on-site contractor must notify Exactus Energy if there are any discrepancies, or damages to the members, that was not addressed in the plan set. The on-site contractor must confirm that the rails will run perpendicular to the rafters.

If you have any further questions, please do not hesitate to contact me.

Acknowledged by:





## DAVID C. HERNANDEZ, PE





513-418-8812 ( 4912 Prospect Ave., Blue Ash OH 45242



davehernandezpe@gmail.com



## **SEISMIC CHECK**

Breakdown of Loads							
Asphalt Shingles:	7	psf					
Insulation:	1.5	psf					
Plywood Sheathing:	1.5	psf					
Rafters:	1	psf					
Misc:	1	psf					
Live load:	20	psf					

Existing Roof Seismic Weight							
	Unit Weight Area						
Element	(psf)	(Sq.ft)	(lbs)				
Roof DL	12	1334.00	16008				
Exterior Walls	45	2160.00	97200				
Interior Walls	12960						
Existing Se	ismic Weight @Roc	of Level, We =	126168				

New PV System Seismic Weight						
Unit Weight Area Weight						
Element	(psf)	(Sq.ft)	(lbs)			
Pv System	3	589.40	1768.20			
Seismic W	eight of New PV Sy	stem, Wpv =	1768.20			

% Increase in Lateral (Seismic) Weight @Roof Level Due to PV System Addition, %-increase = Wpv / We

REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

**APPROVED** 

**Montgomery County** 

**Historic Preservation Commission** 



**COMPANY** 

**PROJECT** 

June 9, 2025 12:35

7129 Maple Ave - Roof 1.wwbu


#### **Design Check Calculation Sheet**

WoodWorks Sizer 13.2.1

#### Loads:

Load	Type	Distribution	Pat-	Location [ft]	Magnitude	Unit
			tern	Start End	Start End	
DL-WOOD	Dead	Full Area	No		12.00(16.0")	psf
DL-PV	Dead	Partial Area	No	0.75 8.50	3.00(16.0")	psf
SL1	Snow	Partial Area	No	0.00 0.75	20.56(16.0")	psf
SL-PV	Snow	Partial Area	No	0.75 8.50	11.09(16.0")	psf
SL2	Snow	Partial Area	No	8.50 11.02	20.56(16.0")	psf
LL1	Roof live	Partial Area	No	0.00 0.75	20.00(16.0")	psf
LL2	Roof live	Partial Area	No	8.50 11.02	20.00(16.0")	psf

#### Maximum Reactions (lbs), Bearing Capacities (lbs) and Bearing Lengths (in):



	•		• •
Unfactored:    Dead    Snow    Roof Live		159 108 30	111 97 57
Factored: Total Bearing:		266	208
F'theta		589	589
Capacity Joist Support Des ratio		773 586	442 586
Joist Support		0.34 0.45	0.47 0.35
Load comb Length		#3 0.50*	#3 0.50*
Min req'd Cb		0.50* 1.75	0.50* 1.00
Cb min Cb support		1.75 1.25	1.00 1.25
Fcp sup		625	625

<sup>\*</sup>Minimum bearing length setting used: 1/2" for end supports and 1/2" for interior supports

#### Lumber-soft, S-P-F, No.1/No.2, 2x10 (1-1/2"x9-1/4")

Supports: All - Timber-soft Beam, D.Fir-L No.2

Roof joist spaced at 16.0" c/c; Total length: 14.99'; Clear span(horz): 1.479', 9.458'; Volume = 1.4 cu.ft.; Pitch: 10/12 Lateral support: top = continuous, bottom = at supports; Repetitive factor: applied where permitted (refer to online help);

This section PASS目

#### APPROVED

Montgomery County

Historic Preservation Commission

REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

#### WoodWorks® Sizer

#### SOFTWARE FOR WOOD DESIGN

7129 Maple Ave - Roof 1.wwbu

WoodWorks® Sizer 13.2.1

Page 2

#### Analysis vs. Allowable Stress and Deflection using NDS 2018:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	fv = 15	Fv' = 155	psi	fv/Fv' = 0.09
Bending(+)	fb = 251	Fb' = 1273	psi	fb/Fb' = 0.20
Bending(-)	fb = 29	Fb' = 591	psi	fb/Fb' = 0.05
Deflection:			_	
Interior Live	0.03 = < L/999	0.62 = L/240	in	0.06
Total	0.11 = < L/999	0.82 = L/180	in	0.14
Cantil. Live	-0.02 = < L/999	0.20 = L/120	in	0.08
Total	-0.05 = L/430	0.26 = L/90	in	0.21

#### **Additional Data:**

```
FACTORS: F/E(psi) CD
                     CM
                           Ct
                                  CL
                                                         Cfrt
                                                                Сi
                                                                     LC#
               1.15 1.00 1.00
Fv'
         135
                                                              1.00
                                                         1.00
Fb'+
                1.15 1.00 1.00 1.000 1.100
          875
                                                    1.15 1.00
                                                              1.00
Fb'-
          875
                                                                      3
               1.15 1.00
                           1.00 0.464 1.100
                                                    1.15
                                                         1.00
                                                               1.00
Fcp'
                           1.00
          425
                      1.00
                                                         1.00
                                                               1.00
Ε'
         1.4 million 1.00
                           1.00
                                                         1.00 1.00
                                                                      3
Emin'
         0.51 million 1.00
                           1.00
                                                         1.00 1.00
```

#### CRITICAL LOAD COMBINATIONS: : LC #3 = D + S

```
Bending(+): LC \#3 = D + S
Bending(-): LC \#3 = D + S
Deflection: LC \#3 = D + S
                            (live)
           LC #3 = D + S
                           (total)
Bearing
         : Support 1 - LC #3 = D + S
            Support 2 - LC #3 = D + S
Load Types: D=dead S=snow Lr=roof live
```

Load combinations: ASD Basic from ASCE 7-16 2.4; all LC's listed in the Analysis report

#### CALCULATIONS:

Shear

```
V \max = 155, V \text{ design} = 136 \text{ (NDS 3.4.3.1(a)) lbs}
M(+) = 447 \text{ lbs-ft; } M(-) = 52 \text{ lbs-ft}
EI = 138.50e06 lb-in^2
"Live" deflection is due to all non-dead loads (live, wind, snow...)
Total deflection = 1.50 permanent + "live"
Bearing: Allowable bearing at an angle F'theta calculated for each support
as per NDS 3.10.3
Lateral stability(-): Lu = 12.38' Le = 20.13' RB = 31.5; Lu based on full span
```

#### **Design Notes:**

- 1. Analysis and design are in accordance with the ICC International Building Code (IBC 2021) and the National Design Specification (NDS 2018), using Allowable Stress Design (ASD). Design values are from the NDS Supplement.
- 2. Please verify that the default deflection limits are appropriate for your application.
- 3. Continuous or Cantilevered Beams: NDS Clause 4.2.5.5 requires that normal grading provisions be extended to the middle 2/3 of 2 span beams and to the full length of cantilevers and other spans.
- 4. Sawn lumber bending members shall be laterally supported according to the provisions of NDS Clause 4.4.1.
- 5. SLOPED BEAMS: level bearing is required for all sloped beams.
- 6. The critical deflection value has been determined using maximum back-span deflection. Cantilever deflections do not govern design.

**APPROVED** 

Montgomery County

**Historic Preservation Commission** 



COMPANY

**PROJECT** 

June 9, 2025 11:49

7129 Maple Ave - Roof 2 - Part 1.wwbu


#### **Design Check Calculation Sheet**

WoodWorks Sizer 13.2.1

#### Loads:

Load	Type	Distribution	Pat-	Location [ft]	Magnitude	Unit
			tern	Start End	Start End	
DL-WOOD	Dead	Full Area	No		9.00(16.0")	psf
DL-PV	Dead	Partial Area	No	2.75 14.23	3.00(16.0")	psf
SL1	Snow	Partial Area	No	0.00 2.75	23.10(16.0")	psf
SL-PV	Snow	Partial Area	No	2.75 14.23	21.95(16.0")	psf
LL1	Roof live	Partial Area	No	0.00 2.75	20.00(16.0")	psf

#### Maximum Reactions (lbs), Bearing Capacities (lbs) and Bearing Lengths (in):



	0 1.5	14.2
Unfactored:		
Dead	121	106
Snow	236	184
Roof Live	74	-1
Factored:		
Total	358	290
Bearing:		
F'theta	453	453
Capacity		
Joist	595	340
Support	586	586
Des ratio		
Joist	0.60	0.85
Support	0.61	0.49
Load comb	#3	#3
Length	0.50*	0.50*
Min req'd	0.31**	0.50*
Cb	1.75	1.00
Cb min	1.75	1.00
Cb support	1.25	1.25
Fcp sup	625	 625

<sup>\*</sup>Minimum bearing length setting used: 1/2" for end supports and 1/2" for interior supports

#### Lumber-soft, S-P-F, No.1/No.2, 2x8 (1-1/2"x7-1/4")

Supports: All - Timber-soft Beam, D.Fir-L No.2

Roof joist spaced at 16.0" c/c; Total length: 15.09'; Clear span(horz): 1.479', 12.658'; Volume = 1.1 cu.ft.; Pitch: 3.75/12 Lateral support: top = continuous, bottom = at supports; Repetitive factor: applied where permitted (refer to online help);

This section PASSES the design code check.

#### APPROVED

Montgomery County

Historic Preservation Commission

Kan Bulit

## REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

<sup>\*\*</sup>Minimum bearing length governed by the required width of the supporting member.

#### WoodWorks® Sizer

#### **SOFTWARE FOR WOOD DESIGN**

7129 Maple Ave - Roof 2 - Part 1.wwbu

WoodWorks® Sizer 13.2.1

Page 2

#### Analysis vs. Allowable Stress and Deflection using NDS 2018:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	fv = 35	Fv' = 155	psi	fv/Fv' = 0.23
Bending(+)	fb = 824	Fb' = 1389	psi	fb/Fb' = 0.59
Bending(-)	fb = 45	Fb' = 716	psi	fb/Fb' = 0.06
Deflection:			_	
Interior Live	0.27 = L/586	0.89 = L/180	in	0.31
Total	0.51 = L/314	1.33 = L/120	in	0.38
Cantil. Live	-0.10 = L/188	0.21 = L/90	in	0.48
Total	-0.19 = L/101	0.31 = L/60	in	0.59

#### **Additional Data:**

```
FACTORS: F/E(psi) CD
                     CM
                           Ct
                                  CL
                                        CF
                                              Cfu
                                                         Cfrt
                                                                Сi
                                                                     LC#
               1.15 1.00 1.00
Fv'
         135
                                                              1.00
                                                         1.00
Fb'+
                1.15 1.00 1.00 1.000 1.200
          875
                                                    1.15 1.00 1.00
Fb'-
          875
                                                                      3
               1.15 1.00
                           1.00 0.516 1.200
                                                    1.15
                                                         1.00
                                                               1.00
Fcp'
                           1.00
          425
                      1.00
                                                         1.00
                                                               1.00
Ε'
         1.4 million 1.00
                           1.00
                                                         1.00 1.00
                                                                      3
Emin'
         0.51 million 1.00
                           1.00
                                                         1.00 1.00
```

#### **CRITICAL LOAD COMBINATIONS:**

: LC #3 = D + S

Load Types: D=dead S=snow Lr=roof live Load combinations: ASD Basic from ASCE 7-16 2.4; all LC's listed in the Analysis report

#### CALCULATIONS:

Shear

```
V max = 280, V design = 255 (NDS 3.4.3.1(a)) lbs
M(+) = 903 lbs-ft; M(-) = 49 lbs-ft
EI = 66.69e06 lb-in^2
"Live" deflection is due to all non-dead loads (live, wind, snow...)
Total deflection = 1.50 permanent + "live"
Bearing: Allowable bearing at an angle F'theta calculated for each support as per NDS 3.10.3
Lateral stability(-): Lu = 13.31' Le = 21.00' RB = 28.5; Lu based on full span
```

#### **Design Notes:**

- 1. Analysis and design are in accordance with the ICC International Building Code (IBC 2021) and the National Design Specification (NDS 2018), using Allowable Stress Design (ASD). Design values are from the NDS Supplement.
- 2. Please verify that the default deflection limits are appropriate for your application.
- 3. Continuous or Cantilevered Beams: NDS Clause 4.2.5.5 requires that normal grading provisions be extended to the middle 2/3 of 2 span beams and to the full length of cantilevers and other spans.
- 4. Sawn lumber bending members shall be laterally supported according to the provisions of NDS Clause 4.4.1.
- 5. SLOPED BEAMS: level bearing is required for all sloped beams.
- 6. The critical deflection value has been determined using maximum back-span deflection. Cantilever deflections do not govern design.

APPROVED

Montgomery County

Historic Preservation Commission

REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025



COMPANY PROJECT

June 9, 2025 11:52

7129 Maple Ave - Roof 2 - Part 2.wwbu


#### **Design Check Calculation Sheet**

WoodWorks Sizer 13.2.1

#### Loads:

Load	Туре	Distribution	Pat-	Location [ft]	Magnitude	Unit
			tern	Start End	Start End	
DL-WOOD	Dead	Full Area			9.00(16.0")	psf
DL-PV	Dead	Partial Area		0.02 10.02	3.00(16.0")	psf
SL-PV	Snow	Partial Area		0.02 10.02	21.95(16.0")	psf
SL2	Snow	Partial Area		10.02 12.74	23.10(16.0")	psf
LL2	Roof live	Partial Area		10.02 12.74	20.00(16.0")	psf

#### Maximum Reactions (lbs), Bearing Capacities (lbs) and Bearing Lengths (in):



Unfactored:		
Dead	105	97
Snow	186	190
Roof Live	8	65
Factored:		-
Total	292	287
Bearing:		-
F'theta	453	453
Capacity		
Joist	340	340
Support	586	586
Des ratio		
Joist	0.86	0.84
Support	0.50	0.49
Load comb		#3
Length	0.50*	0.50*
Min req'd	0.50*	0.50*
Cb	1.00	1.00
Cb min	1.00	1.00
Cb support	1.25	1.25
Fcp sup	625	625

\*Minimum bearing length setting used: 1/2" for end supports

#### Lumber-soft, S-P-F, No.1/No.2, 2x8 (1-1/2"x7-1/4")

Supports: All - Timber-soft Beam, D.Fir-L No.2

Roof joist spaced at 16.0" c/c; Total length: 13.54'; Clear span(horz): 12.658'; Volume = 1.0 cu.ft.; Pitch: 3.75/12 Lateral support: top = continuous, bottom = at supports; Repetitive factor: applied where permitted (refer to online help);

This section PASSES the design code check.

#### **APPROVED**

Montgomery County

Historic Preservation Commission

REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

#### WoodWorks® Sizer

#### SOFTWARE FOR WOOD DESIGN

7129 Maple Ave - Roof 2 - Part 2.wwbu

WoodWorks® Sizer 13.2.1

Page 2

#### Analysis vs. Allowable Stress and Deflection using NDS 2018:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	fv = 35	Fv' = 155	psi	fv/Fv' = 0.22
Bending(+)	fb = 843	Fb' = 1389	psi	fb/Fb' = 0.61
Live Defl'n	0.28 = L/563	0.89 = L/180	in	0.32
Total Defl'n	0.52 = L/307	1.33 = L/120	in	0.39

#### Additional Data:

```
CF
                                                           Cr Cfrt
FACTORS: F/E(psi) CD
                          CM
                                Ct
                                       CL
                                                                         Ci
                                                     Cfu
                                                                                LC#
                 1.15 1.00 1.00
                                                                  1.00 1.00
Fv'
           135
Fb'+
           875
                  1.15 1.00 1.00 1.000 1.200
                                                                 1.00 1.00
         425 - 1.00 1.00 - - - 1.4 million 1.00 1.00 - - - 0.51 million 1.00 1.00 - -
                                                                 1.00 1.00
1.00 1.00
Fcp'
Ε'
                                                                  1.00 1.00
Emin'
```

#### **CRITICAL LOAD COMBINATIONS:**

```
Shear : LC #3 = D + S
Bending(+): LC #3 = D + S
Deflection: LC #3 = D + S (live)
    LC #3 = D + S (total)
Bearing : Support 1 - LC #3 = D + S
    Support 2 - LC #3 = D + S
Load Types: D=dead S=snow Lr=roof live
```

Load combinations: ASD Basic from ASCE 7-16 2.4; all LC's listed in the Analysis report

#### CALCULATIONS:

```
V max = 278, V design = 252 (NDS 3.4.3.1(a)) lbs; M(+) = 923 lbs-ft EI = 66.69e06 lb-in^2 "Live" deflection is due to all non-dead loads (live, wind, snow...) Total deflection = 1.50 permanent + "live" Bearing: Allowable bearing at an angle F'theta calculated for each support as per NDS 3.10.3
```

#### **Design Notes:**

- 1. Analysis and design are in accordance with the ICC International Building Code (IBC 2021) and the National Design Specification (NDS 2018), using Allowable Stress Design (ASD). Design values are from the NDS Supplement.
- 2. Please verify that the default deflection limits are appropriate for your application.
- 3. Sawn lumber bending members shall be laterally supported according to the provisions of NDS Clause 4.4.1.
- 4. SLOPED BEAMS: level bearing is required for all sloped beams.

**APPROVED** 

Montgomery County

Historic Preservation Commission



**COMPANY** 

**PROJECT** 

June 9, 2025 11:55

7129 Maple Ave - Roof 3.wwbu


#### **Design Check Calculation Sheet**

WoodWorks Sizer 13.2.1

#### Loads:

Load	Type	Distribution	Pat-	Location [ft]	Magnitude	Unit
			tern	Start End	Start End	
DL-WOOD	Dead	Full Area	No		12.00(16.0")	psf
DL-PV	Dead	Partial Area	No	1.75 5.00	3.00(16.0")	psf
SL1	Snow	Partial Area	No	0.00 1.75	20.56(16.0")	psf
SL-PV	Snow	Partial Area	No	1.75 5.00	11.09(16.0")	psf
SL2	Snow	Partial Area	No	5.00 6.52	20.56(16.0")	psf
LL1	Roof live	Partial Area	No	0.00 1.75	20.00(16.0")	psf
LL2	Roof live	Partial Area	No	5.00 6.52	20.00(16.0")	psf

#### Maximum Reactions (lbs), Bearing Capacities (lbs) and Bearing Lengths (in):



	U	1.5	0.5
Unfactored:			
Dead		100	59
Snow		87	50
Roof Live		56	31
Factored:			
Total		188	109
Bearing:			
F'theta		622	622
Capacity			
Joist		817	467
Support		586	586
Des ratio			
Joist		0.23	0.23
Support		0.32	0.19
Load comb		#3	#3
Length		0.50*	0.50*
Min req'd		0.50*	0.50*
Cb		1.75	1.00
Cb min		1.75	1.00
Cb support		1.25	1.25
Fcp sup		625	625

\*Minimum bearing length setting used: 1/2" for end supports and 1/2" for interior supports

**REVIEWED** 

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

APPROVED

Montgomery County

Historic Preservation Commission

#### WoodWorks® Sizer

#### SOFTWARE FOR WOOD DESIGN

7129 Maple Ave - Roof 3.wwbu

WoodWorks® Sizer 13.2.1

Page 2

#### Lumber-soft, S-P-F, No.1/No.2, 2x8 (1-1/2"x7-1/4")

Supports: All - Timber-soft Beam, D.Fir-L No.2

Roof joist spaced at 16.0" c/c; Total length: 9.4'; Clear span(horz): 1.479', 4.958'; Volume = 0.7 cu.ft.; Pitch: 11/12 Lateral support: top = continuous, bottom = at supports; Repetitive factor: applied where permitted (refer to online help); This section PASSES the design code check.

#### Analysis vs. Allowable Stress and Deflection using NDS 2018:

Criterion	Analysis Value	Design Value	Unit	Analysis/Design
Shear	fv = 10	Fv' = 155	psi	fv/Fv' = 0.06
Bending(+)	fb = 100	Fb' = 1389	psi	fb/Fb' = 0.07
Bending(-)	fb = 50	Fb' = 1041	psi	fb/Fb' = 0.05
Deflection:				
Interior Live	0.00 = < L/999	0.45 = L/180	in	0.01
Total	0.02 = < L/999	0.68 = L/120	in	0.02
Cantil. Live	-0.00 = < L/999	0.27 = L/90	in	0.01
Total	-0.01 = < L/999	0.41 = L/60	in	0.03

#### Additional Data:

Shear

```
FACTORS: F/E(psi) CD
                       CM
                             Ct
                                                           Cfrt
                                                                  Сi
                                                                       LC#
               1.15 1.00
Fv'
          135
                            1.00
                                                           1.00
                                                                1.00
                                                                        3
Fb'+
          875
                            1.00 1.000
                                        1.200
                                                     1.15
                 1.15
                      1.00
                                                           1.00
                                                                1.00
Fb'-
          875
               1.00 1.00
                           1.00 0.862 1.200
                                                     1.15
                                                          1.00
                                                                1.00
                      1.00
                                                           1.00
Fcp'
          425
                            1.00
                                                                1.00
Ε'
          1.4 million
                      1.00
                            1.00
                                                           1.00
                                                                1.00
         0.51 million
Emin'
                      1.00
                                                                1.00
                            1.00
                                                           1.00
```

#### CRITICAL LOAD COMBINATIONS: : LC #3 = D + S

Bending(+): LC #3 = D + SBending(-): LC #2 = D + Lr Deflection: LC #3 = D + S(live) LC #3 = D + S(total) : Support 1 - LC #3 = D + S Bearing Support 2 - LC #3 = D + S

Load Types: D=dead S=snow Lr=roof live

Load combinations: ASD Basic from ASCE 7-16 2.4; all LC's listed in the Analysis report CALCULATIONS:

 $V \max = 88$ , V design = 72 (NDS 3.4.3.1(a)) lbsM(+) = 109 lbs-ft; M(-) = 54 lbs-ft $EI = 66.69e06 lb-in^2$ "Live" deflection is due to all non-dead loads (live, wind, snow...) Total deflection = 1.50 permanent + "live" Bearing: Allowable bearing at an angle F'theta calculated for each support

as per NDS 3.10.3

Lateral stability(-): Lu = 6.81' Le = 11.56' RB = 21.2; Lu based on full span

#### **Design Notes:**

- 1. Analysis and design are in accordance with the ICC International Building Code (IBC 2021) and the National Design Specification (NDS 2018), using Allowable Stress Design (ASD). Design values are from the NDS Supplement.
- 2. Please verify that the default deflection limits are appropriate for your application.
- 3. Continuous or Cantilevered Beams: NDS Clause 4.2.5.5 requires that normal grading provisions be extended to the middle 2/3 of 2 span beams and to the full length of cantilevers and other spans.
- 4. Sawn lumber bending members shall be laterally supported according to the provisions of NDS Clause 4.4.1.
- 5. SLOPED BEAMS: level bearing is required for all sloped beams.
- 6. The critical deflection value has been determined using maximum back-span deflection. Cantilever deflections do not govern design.

#### **APPROVED**

Montgomery County

**Historic Preservation Commission** 

Kare Bulit

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

#### ASCE 7 - 16 WIND CALCULATION FOR: Roof 1 & Roof 3

Project Address: 7129 Maple Ave, Takoma Park, MD 20912, USA

#### **DESIGN CRITERIA**

Ultimate Wind Speed: 115 mph

Exposure Category: B

a: 3 ft

Velocity Pressure Exposure Coefficient, Kz: 0.61

Wind Directionality Factor, Kd: 0.85

Ground Elevation Factor, Ke: 1

Topographic Factor, Kzt: 1

Solar Array Pressure Equalization Factor, ya: 0.65

Array Edge Factor, γE: 1

Solar Array Dead Load: 3 psf

Mean Roof Height: 18 ft

Roof Pitch: 41°

Roof Type: Gable

Module Name, Dimensions, Area: MSE410HT0B, 44.65in X

67.8in, 3027.27 sqin

#### **CALCULATION**

 $q_h \, = \, 0.00256(Kz)(Kzt)(Kd)(I)(V^2)$ Velocity Pressure Due to Wind:  $(Ch\ 26.Eq\ 26.10-1)$ Actual Uplift Pressure: p = 0.6D + 0.6W(Ch 2.4.1 LC #7/a) Wind Uplift Pressure: p = qh (GCp)(yE)(ya) $(Ch\ 29.Eq\ 29.4-7)$ 

#### Landscape / Portrait Panels

Roof Zone	1	2e	2n	2r	3e	3r
Mount Spacing	67.8"	67.8"	67.8"	67.8"	67.8"	67.8"
External Pressure Coefficient (GCp)	-1.78	-1.78	-1.98	-1.78	-2.47	-1.98
Actual Uplift Pressure (p)	-16 psf	-16 psf	-16 psf	-16 psf	-15.55 psf	-16 psf
Tributary Area (AT)	10.51 sqft					
Uplift Force (P)	-168.18 lbs	-168.18 lbs	-168.18 lbs	-168.18 lbs	-163.43 lbs	-168.18 lbs

#### **Uplift Capacity**

Attachment Type = 4pcs #14 Wood Screw 0.75" TopSpeed

Mount Assembly

Hardware Pullout Capacity = 258 lbs

Safety Factor = 3

Maximum Uplift Force = 168.182 lbs Allowable Pullout Capacity = 258 lbs

Allowable Pullout Capacity = 258 lbs > Uplift Force per Bolt = 168.18 lbs, Therefore OK.

**APPROVED** 

Montgomery County

**Historic Preservation Commission** 



#### **ASCE 7 - 16 WIND CALCULATION FOR: Roof 2**

Project Address: 7129 Maple Ave, Takoma Park, MD 20912, USA

#### **DESIGN CRITERIA**

Ultimate Wind Speed: 115 mph

Exposure Category: B

a: 3 ft

Velocity Pressure Exposure Coefficient, *Kz*: 0.61 Topographic Factor, *Kzt*: 1

Wind Directionality Factor, Kd: 0.85

Ground Elevation Factor, Ke: 1

Solar Array Pressure Equalization Factor, ya: 0.65

Array Edge Factor, γE: 1

Solar Array Dead Load: 3 psf

Mean Roof Height: 18 ft

Roof Pitch: 13°

Roof Type: Gable

Module Name, Dimensions, Area: MSE410HT0B, 44.65in X

67.8in, 3027.27 sqin

#### **CALCULATION**

Velocity Pressure Due to Wind:  $q_h = 0.00256(Kz)(Kzt)(Kd)(l)(V^2)$   $(Ch\ 26.Eq\ 26.10-1)$  Actual Uplift Pressure: p = 0.6D + 0.6W  $(Ch\ 2.4.1\ LC\ \#7/a)$  Wind Uplift Pressure:  $p = qh\ (GCp)(yE)(ya)$   $(Ch\ 29.Eq\ 29.4-7)$ 

#### Landscape / Portrait Panels

Roof Zone	1	2e	2n	2r	3e	3r
Mount Spacing	67.8"	67.8"	67.8"	67.8"	67.8"	67.8"
External Pressure Coefficient (GCp)	-2	-2	-2.97	-2.97	-2.97	-3.56
Actual Uplift Pressure (p)	-16 psf	-16 psf	-18.56 psf	-18.56 psf	-18.56 psf	-22.61 psf
Tributary Area (AT)	10.51 sqft					
Uplift Force (P)	-168.18 lbs	-168.18 lbs	-195.05 lbs	-195.05 lbs	-195.05 lbs	-237.62 lbs

#### **Uplift Capacity**

Attachment Type = 4pcs #14 Wood Screw 0.75" TopSpeed

Mount Assembly

Hardware Pullout Capacity = 258 lbs

Safety Factor = 3

Maximum Uplift Force = 237.623 lbs

Allowable Pullout Capacity = 258 lbs

Allowable Pullout Capacity = 258 lbs > Uplift Force per Bolt = 237.62 lbs, Therefore OK.

**APPROVED** 

Montgomery County

Historic Preservation Commission

Kare Bulit



By Laura DIPasquale at 2:20 pm, Jul 24, 2025



# Solar Energy World Because Tomorrow Matters

Project_Roof Mounted Solar PV Installation	Property Owner Brian Levy
Address 7129 Maple Ave, Takon	

☑ I reviewed the design of the photovoltaic (PV) system, as designed by the manufacturer, and the design criteria utilized for the mounting equipment and panel mounting assembly (rack system) for the installation of (28) panels supported by the rack system, as shown on the drawings prepared for the above referenced address. I certify that the configurations and design criteria meet the standards and requirements of the International Residential Code (IRC) in COMCOR 08.00.02.

✓ The attachment of the rack system to the building at the above address, including the location, number, and type of attachment points; the number of fasteners per attachment point; and the specific type of fasteners (size, diameter, length, minimum embedment into structural framing, etc.) meets the standards and requirements of the IRC adopted by Montgomery County in COMCOR 08.00.02.

☑ I evaluated the existing roof structure of the building at the above address and analyzed its capacity to support the additional loads imposed by the PV system. I certify that no structural modifications of the existing roof structure are required. The existing roof structure meets the standards and requirements of the IRC, adopted by Montgomery County in COMCOR 08.00.02, necessary to support the PV system.

□ I evaluated the existing roof structure of the building at the above address and analyzed its capacity to support the additional loads imposed by the PV system. Structural modifications of the existing roof structure are required. I certify that the roof structure, as modified on the drawings for this project, will support the additional loads imposed by the PV system. I further certify that design of the modified roof structure meets the standards and requirements of the IRC, adopted by Montgomery County in COMCOR 08.00.02.

✓ I prepared or approved the construction documents for the mounting equipment, rack system, roof structure for this project.

#### Re-installations:

 $\Box$  I certify that the reinstallation of the photovoltaic system (PV) as shown on the approved drawings for permit \_\_\_\_\_ (show original permit #) does not alter the approval under the permit or make the PV system, attachment to the building, and roof framing unsafe.

49993		
Maryland	PE License	Number

Date \_06/09/2025

Seal

David C. Hernandez, Digitally signed by David C. Hernandez, David



PROFESSIONAL CERTIFICATION 1 HERGE CERTIFY THAT THESE DOCUMENTS WER PREPARED OR APPROVED BY ME, AND THAT AM A DULY LICENSED PROFESSIONA ENGINEER UNDER THE LAWS OF THE STATE O MARYLAND, LICENSE NO. 4999, 1929, 1008/001

APPROVED

Montgomery County

Historic Preservation Commission

Kare Bulit

Updated 11/14/2024

REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025



Property Owners Name: Brian Levy
Property Owners Address: 7129 Maple Avenue, Takoma Park, MD 20912
Address of installation if different than owner's address:
I certify that:  ✓ I prepared or approved the electrical drawings and related documents for the photovoltaic {PV} system at the above location.  ✓ The design of the PV system, and all electrical Installations and equipment, meets the standards and requirements of the National Electrical Code as adopted by Montgomery County <i>in</i> COMCOR 17.02.01.  ✓ I reviewed and completed the Worksheet for PV System, which was attached to the permit application for the PV system at the above location.
15732
State Master Electrician License Number
Date: 06/12/2025
Signature: Matt Hum

REVIEWED www.solarenergyworld.com

410.579.2

# City of Takoma Park

## Housing and Community Development Department

Main Office 301-891-7119 Fax 301-270-4568 www.takomaparkmd.gov



7500 Maple Avenue Takoma Park, MD 20912

#### MUNICIPALITY LETTER

June 13, 2025

To: Brian Levy

7129 Maple Avenue, Takoma Park, MD 20912

levybd@gmail.com

202-247-5106

To: Department of Permitting Services

2425 Reedie Drive, 7<sup>th</sup> floor Wheaton, Maryland 20902

From: Planning and Development Services Division

#### THIS IS NOT A PERMIT - For Informational Purposes Only

#### VALID FOR ONE YEAR FROM DATE OF ISSUE

The property owner is responsible for obtaining all required permits from Montgomery County and the City of Takoma Park. If this property is in the **Takoma Park Historic District**, it is subject to Montgomery County Historic Preservation requirements.

Representative Name: tina Crouse-Solar Energy World tcrouse@solarenergyworld.com 410-570-4157

**Location of Project:** 7129 Maple Avenue, Takoma Park, MD 20912

Proposed Scope of Work: Install (28) roof mounted solar panels, 11.48 kW

The purpose of this municipality letter is to inform you that the City of Takoma Park has regulations and city permit requirements that may apply to your project. This municipality letter serves as notification that, in addition to all Montgomery County requirements, you are required to comply with all City permitting requirements, including:

- Tree Impact Assessment/Tree Protection Plan
- Stormwater management
- City Right of Way

Failure to comply with these requirements could result in the issuance of a Stop Work Order and other administrative actions within the provisions of the law. Details of Takoma Park's permit requirements are attached on page 2.

The iscuspes of this letter does not indicate approval

REVIEWED

Wonlgomery County review process.

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

ATTROVED

Montgomery County

Historic Preservation Commission

authorize the property owner to project plans during the

## City Of Takoma Park

#### The City of Takoma Park permits for the following issues:

#### Tree Impact Assessment/Tree Protection Plan/Tree Removal Application:

Construction activities that occur within 50 feet of any urban forest tree (7 and 5/8" in trunk diameter or greater), located on the project property or on an adjacent property, may require a Tree Impact Assessment and possibly a Tree Protection Plan Permit. Make sure to submit a request for a Tree Impact Assessment and schedule a site visit with the City's Urban Forest Manager if any urban forest tree is in the vicinity of proposed construction activities. See the Tree Permits section of the City website for the specific conditions in which a Tree Impact Assessment is required. Depending on the Urban Forest Manager's conclusion following the Tree Impact Assessment, you may need to prepare a full Tree Protection Plan and apply for a Tree Protection Plan Permit as well. Separately, the removal of any urban forest tree will require a Tree Removal Permit application. The tree ordinance is detailed in the City Code, section 12.12. For permit information check: https://takomaparkmd.gov/services/permits/tree-The City's Urban Forest Manager can be reached 301-891-7612 urbanforestmanager@takomaparkmd.gov.

#### Stormwater Management:

If you plan to develop or redevelop property, you may be required to provide appropriate stormwater management measures to control or manage runoff, as detailed in City Code section 16.04. All commercial or institutional development in the city must apply for a Stormwater Management Permit regardless of the size of the land disturbance. Additions or modifications to existing detached single-family residential properties do not require a Stormwater Management permit if the project does not disturb more than 5,000 square feet of land area. For more information visit: <a href="https://takomaparkmd.gov/government/public-works/stormwater-management-program/">https://takomaparkmd.gov/government/public-works/stormwater-management-program/</a>. The City Engineer should be contacted to determine if a City permit is required. The City Engineer can be reached at 301-891-7620.

#### City Right of Way:

- To place a construction dumpster or storage container temporarily on a City right of way (usually an
  adjacent road), you will need to obtain a permit. A permit is not required if the dumpster is placed in a
  privately-owned driveway or parking lot.
- If you plan to install a new **driveway apron**, or enlarge or replace an existing driveway apron, you need a Driveway Apron Permit.
- If you plan to construct a **fence** in the City right of way, you need to request a Fence Agreement. If approved, the Agreement will be recorded in the Land Records of Montgomery County.

For more information and applications for City permits, see: <a href="https://takomaparkmd.gov/services/permits/">https://takomaparkmd.gov/services/permits/</a> or contact the Department of Public Works at 301-891-7633.

Failure to comply with the City's permitting requirements could result in the issuance of a Stop Work Order and other administrative actions within the provisions of the law.





Marc Elrich
County Executive

Rabbiah Sabbakhan Director

### HISTORIC AREA WORK PERMIT APPLICATION

Application Date: 6/19/2025

Application No: 1121920

AP Type: HISTORIC Customer No: 1408761

#### Affidavit Acknowledgement

The Contractor is the Primary applicant authorized by the property owner This application does not violate any covenants and deed restrictions

#### **Primary Applicant Information**

Address 7129 MAPLE AVE

TAKOMA PARK, MD 20912

Othercontact Solar Energy World (Primary)

#### **Historic Area Work Permit Details**

Work Type ALTER

Scope of Work Install (28) roof mounted solar panels, 11.48 kW

APPROVED

Montgomery County

Historic Preservation Commission


REVIEWED

2425 Reedie Drive, 7th Floor. Wheaton.

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

Kare Bulit

777-6256 TTY



# Solar Mounting Solutions

TopSpeed™ Mounting System

**Installation Manual** 

snapnrack.com

**APPROVED** 

**Montgomery County** 

**Historic Preservation Commission** 

**REVIEWED** 

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

#### An Intro to SnapNrack TopSpeed™ with SpeedSeal™ Technology



SnapNrack's primary goal is to provide our customers with the lowest possible installed cost for mounting residential solar modules, without compromising the values the industry has come to expect: ease of use, quality, aesthetics, and safety. Designing with this goal in mind, we are proud to present the SnapNrack TopSpeed™ mounting system with SpeedSeal™ Technology.

SnapNrack has created a ground breaking system combining great features and benefits we are known for, with our TopSpeed™ System and the most up to date technical innovation in the industry, thus reducing parts while driving down labor, material, and total installation costs. Designed to work with standard module frames, achieving UL 2703 Listing for Grounding/Bonding and Fire Classification, providing integrated wire management, aesthetics and our industry leading "Snap-In" features, SnapNrack is providing the simplest and most cost effective solar mounting solution on the market with TopSpeed™ including integrated fasteners and SpeedSeal™ Technology.

#### Advantages of Installing the SnapNrack TopSpeed™ System

Modules are installed with a minimum number of parts

This elimination of parts leads to a lower estimated system cost for both the installer and home owner.

**Built in Wire Management and Aesthetics** 

Extensive wire management solutions have been designed specifically for the system that adapts to multiple possible mounting positions.

The system is designed to be aesthetically pleasing and sturdy with a skirt that provides considerable strength at the leading edge and an elegant look for those seeking high end looking systems.

SnapNrack TopSpeed™ includes SpeedSeal™ Technology

SpeedSeal™ Technology features integrated flashing. This eliminates loosening layers of composition and removing nails with a pry bar, leading to less damage to the roof, minimized potential roof leaks, and much faster installs.

**TopSpeed™ Mounts attach Directly to the Decking** 

As well as all of the benefits associated with the standard SpeedSeal™ Technology, TopSpeed™ attaches to the roof sheathing and does not require rafter attachment. Simply attaching to the roof sheathing removes the requirement for finding rafters and drilling pilot holes, creating potential rafter misses that can cause leaks.

REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

**APPROVED** 

Montgomery County

**Historic Preservation Commission** 

# Table of Contents



Pro	iect	Plans

Certification Details	4
Component Details	5
Pre-Installation Requirements	7
Installation Steps	
TopSpeed™ Skirt Layout	8
TopSpeed™ Mount to Module Installation	9
TopSpeed <sup>™</sup> Mount Skirt Installation	0
Wire Management	3
MLPE Attachment	6
Module Installation	9
Grounding Specifications	2
Maintaining the Grounding Bonding When Removing a Module	3
Appendix A: List of approved Modules and MLPEs	5

\_\_\_\_

Montgomery County

Historic Preservation Commission

APPROVED

**REVIEWED** 

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

#### Certification Details



SnapNrack TopSpeed™ mounting system has been evaluated by Underwriters Laboratories (UL) and Listed to UL Standard 2703 for Grounding/Bonding, and Fire Classification.

#### **Grounding/Bonding**

Only specific components have been evaluated for bonding, and are identified as being in the ground path. The TopSpeed™ components that have been evaluated for bonding are the Mount Assembly (Mount Clamp Top, Module Clamp Tower, Angle Bracket), Clamp Assembly, Universal Skirt, Universal Skirt Clamp, Ground Lugs, and Smart Clips.

Universal Skirt Spacers, Mount Channel Nut, and Mount Base are not required to be bonded to the system based on the exceptions in clause 9.1 of UL 2703 1st Ed. Wire management clips are utilized to route conductors away from these components and must be assembled according to the instructions.

This mounting system may be used to ground and/or mount a PV module complying with UL 1703 or UL 61703 only when the specific module has been evaluated for grounding and/or mounting in compliance with the included instructions. See Appendix A for the list of modules tested for use with the TopSpeed™ System for integrated grounding.

Ground Lugs have been evaluated to both UL 467 and UL 2703 Listing requirements. The following ground lugs have been approved for use: SnapNrack model 242-92202, and Ilsco models GBL-4DBT and SGB-4.

The following components have been evaluated for bonding as the fault current ground path: TopSpeed™ Mount Assembly, (Mount Clamp Top, Module Clamp Tower, Angle Bracket), Clamp Assembly, Wire Management Clips, and Ground Lugs. In order to maintain the Listing for bonding, wire management clips must be assembled to route conductors away from parts that have not been evaluated for bonding.

A Listed (QIMS) and Unlisted Component (KDER3) grounding lug, SnapNrack part no. 242-92202, is attached to the module frame flange for the normal attachment of a Grounding Electrode Conductor, which provides bonding within the system and eventual connection to a Grounding Electrode, as required by the U.S. NEC. Details of part no. 242-92202 can be found in Volume 1, Section 4, and Volume 2, Section 2. When this method is used, the grounding symbol is stamped onto the body of the ground lug to identify the grounding terminal.

An alternate method of grounding, a UL Listed (KDER and QIMS) grounding lug, Ilsco (E34440 and E354420) model SGB-4 is attached to the module frame flange. When this method is used, the grounding terminal is identified by the green colored screws of the lug.

An alternate method of grounding, a UL Listed (KDER and QIMS) grounding lug, Ilsco (E34440 and E354420) model GBL-4BDT is attached to the module frame flange through the specified hardware and torque values. When this method is used, the grounding terminal is identified by the green colored set screw of the lug.

An alternate method of grounding, Enphase R/C (QIKH2)(QIMS2) model M250, M215 & C250 is bonded to the Listed PV module frame by the Enphase R/C (QIMS2) Model EFM-XXMM anodization piercing mounting/clamping kit. The total roof-mounted PV system is bonded (modules and microinverters) together and the assembly is bonded to ground through the Enphase R/C (QIMS2) Engage Cables; Model ETXX-240, ETXX-208 or ETXX-277, when properly grounded at the service entrance. R/C (QIMS2), Dynoraxx (E357716) photovoltaic bonding device cat. no. Dynobond is an optional component that may be used with this system. The Dynobond device has been evaluated to provide module to module bonding. The Dynobond device attaches to the frame flange of adjacent modules Listed (QIMS), SnapNrack MLPE Frame Attachment Kit model 242-02151 has been investigated to bond approved MLPE device back plates to frames of

REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

**APPROVED** 

Montgomery County

Historic Preservation Commission



#### **Fire**

SnapNrack TopSpeed™ has been investigated for a Class A System Fire Classification for Steep-Sloped and low sloped roofs with Type 1 and Type 2 modules. Because the system was tested at 5 inches above the test roof fixture, TopSpeed™ can be installed without any height restrictions due to System Fire Classification. See Appendix A for potential module-specific height restrictions due to module temperature. The Skirt is considered an optional component with respect to Fire Classification, as SnapNrack TopSpeed™ maintains the same Fire Classification Rating both with and without the skirt.

**NOTE:** Modules with an asterisk\* have a fire rating that is different from Type 1, Type 2 or Type 29. SNR systems have only been evaluated for use with Type 1, Type 2, or Type 29 modules. Modules with a different fire type rating should be considered to not have been evaluated for use with SNR systems with respect to a system fire rating.

#### **Inspection Practices**

SnapNrack recommends a periodic re-inspection of the completed installation for loose components, loose fasteners, and any corrosion, such that if found, the affected components are to be immediately replaced.

REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

**APPROVED** 

Montgomery County

Historic Preservation Commission

#### **TopSpeed™ Structural Components**



**TopSpeed™ Mount** 

SnapNrack TopSpeed™ Mount assembly including SpeedSeal™ base, clamp top, and (4) SnapNrack #14 SS Wood Screws with 1/2" Hex Head.



**TopSpeed™ Clamp** 

SnapNrack TopSpeed™ Clamp assembly including including Link bottom, Link top, and springs.



**Universal Skirt** 

SnapNrack Universal Skirt in double portrait or single landscape lengths.

#### **Wire Managements Components**



**Skirt Spacers** 

SnapNrack Universal Skirt Spacer for 40mm, 38mm, 35mm, 32mm, and 30mm modules.



**Smart Clip** 

Module frame cable clip, holds two PV wires or Enphase IQ-Cables.



**Smart Clip XL** 

Module frame cable clip, holds six PV wires or four Enphase IQ-Cable.



**Wire Saver** 

Designed to secure conductors that become loose and hang below the array, holds one conductor.

#### **Grounding/MLPE Components**



**Ground Lug** 

SnapNrack Ground Lug assembly used for attaching the Equipment Grounding Conductor on to one

module or any per array. 5



**MLPE Frame Attachment Kit** 

Attaches MLPEs (Module Level Performance Enhancers) and other related equipment to the module

me.

#### APPROVED

Montgomery County

Historic Preservation Commission

REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

## **Hardware Torque Specifications**

The recommended torque to be applied to components for proper assembly and bonding are as follows:

Hardware Description	Torque Specification
All TopSpeed™ ½" bolts; System Leveling Bolt, TopSpeed™ Mount Clamping Bolt, Clamp Bolt	16 ft-lb
Ground Lug model 242-92202 to Module Frame or anywhere on the TopSpeed™ Mount, and Ground Lug model 242-92202 to Grounding Electrode Conductor (6-12 SOL)	8 ft-lb
MLPE Frame Attachment Kit, MLPE Rail Attachment Kit	10 ft-lb
SolarEdge Frame Mounted Microinverter Bracket to Module Frame	11 ft-lb
Enphase Frame Mounted Microinverter Bracket to Module Frame	13 ft-lb
Ground Lug model SGB-4 to module	75 in-lb
Ground Lug model SGB-4 to Grounding Electrode Conductor (4-14 SOL or STR)	35 in-lb
Ground Lug model GBL-4DBT to module	35 in-lb
Ground Lug model GBL-4DBT to Grounding Electrode Conductor (10-14 SOL or STR)	20 in-lb
Ground Lug model GBL-4DBT to Grounding Electrode Conductor (8 SOL or STR)	25 in-lb
Ground Lug model GBL-4DBT to Grounding Electrode Conductor (4-6 SOL or STR)	35 in-lb

6

APPROVED

Montgomery County

Historic Preservation Commission

W. W. lit

## **Site Survey**

- Measure the roof surfaces and develop an accurate drawing, including any obstacles such as chimneys and roof vents.
- If plans for the roof structure are available, verify that the plans match the final structure.
- $\bullet$  Identify any roof access or setback areas as required by the local AHJ.
- Identify any construction issues that may complicate the process of locating rafters from the roof surface.
- If you find structural problems such as termite damage or cracked rafters that may compromise the structure's integrity consult a structural engineer.

## **Design Guidance**

- PV Designers should account for the 0.75 inch spacing between rows and columns of modules when creating the layout.
- Determine site conditions for calculating the engineering values, confirm site conditions and code versions comply with local AHJ requirements.
- Reference site conditions and system specifications in TopSpeed™ Structural Engineering Report to determine the number of attachments per module side.
- Insert SnapNrack installation details into design plan set specific to the project requirements.
- Draw roof attachment locations on plan set layout based on TopSpeed™ Structural Engineering.

## **②** Best Practice:

If environmental load conditions require three TopSpeed™ attachments per module side this is only required when modules share attachments.

- Identify homerun and Junction Box locations based on rooftop wiring requirements.
- Mark distance from array edge to identifiable roof feature in x and y axes.

## ♠ Safety Guidance

- Always wear appropriate OSHA approved safety equipment when at active construction site.
- Appropriate fall protection or prevention gear should be used. Always use extreme caution when near the edge of a roof.
- Use appropriate ladder safety equipment when accessing the roof from ground level.





Image note: X-Axis described in this manual is cross-slope on the roof, Y-Axis is in line with the roof slope.






Image note: This four module array is installed in a high load configuration with three attachments per side where two modules share attachments. See highlighted area. As shown, three attachments are never required at the skirt or the top of the array.

## ⚠ Safety Guidance Continued

Safety equipment should be checked periodically for wear

### **APPROVED**

Montgomery County
Historic Preservation Commission

tection when required.

REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

## **TopSpeed™ Mount to Module Frame Installation**

snapnrack.com

## **Required Tools**

- Socket Wrench/Impact Driver
- Torque Wrench


● 1/2" Socket

## Materials Included - TopSpeed™ System with SpeedSeal™ Technology


- **1** (1) SnapNrack TopSpeed™ Mount
- (4) SnapNrack #14 Wood Screw with 1/2" Hex Head & sealing washer

## Best Practice:


Attach all TopSpeed™ mounts as the modules are being prepped with MLPEs on the ground. Attach Mounts before attaching MLPEs to simplify wire management.




## INSTALLATION INSTRUCTIONS



1) Assemble all TopSpeed™ Mounts required for the installation. Slide the clamp tower assembly into the angle bracket riser and tighten the leveling bolt to 16 ft-lbs.



2) Position TopSpeed™ Mount clamp on the module frame within the module manufacturers required clamping zone.



3) Tighten 1/2" clamping bolt to 16 ft-lb. Only two Mounts are required per module on one side.



## Install Note:

For high load conditions add a third attachment in the middle of the module frame.

## REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

**APPROVED** 

Montgomery County

**Historic Preservation Commission** 

## TopSpeed™ Universal Skirt Layout

snapnrack.com

## **Required Tools**

Roof Marking Crayon or Chalk Tape Measure


### LAYOUT INSTRUCTIONS

1) Use a tape measure to verify that all modules will fit properly on the roof surface.

2) On the roof draw the layout for the skirt installation including module gaps (recommended 0.75 inch gap), bottom corners, and locations of the two TopSpeed™ attachments per module that clamp to the skirt. Three attachments per module is never required at the skirt.

## nstall Note:

If environmental load conditions require three TopSpeed™ attachments per module side this is only required when modules share attachments.



### **APPROVED**

**Montgomery County** 

**Historic Preservation Commission** 

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

**REVIEWED** 

## **TopSpeed™ Mount: Skirt Installation**

snapnrack.com

## **Required Tools**

- Socket Wrench/Impact Driver
- Torque Wrench
- 1/2" Socket
- Roofing sealant


## Materials Included - TopSpeed™ Mount with SpeedSeal™ Technology



- 2 (1) TopSpeed™ Clamp
- (1) Universal Skirt
- 4 (1) Universal Skirt Spacers




















## **APPROVED**

**Montgomery County** 


**Historic Preservation Commission** 

## **REVIEWED**


## **TopSpeed™ Mount Skirt Installation**

snapnrack.com


## **INSTALLATION INSTRUCTIONS**



1) Install TopSpeed™ Mounts at locations drawn during the skirt layout. Mounts must be installed entirely on one course of composition.




2) Fill both cavities on bottom of TopSpeed™ Mount created by SpeedSeal™ gasket with roof sealant to ensure a watertight seal.




3) Attach TopSpeed™ Mount to roof using the (4) SnapNrack #14 Wood Screws with 1/2" hex head that are captured in the Mount.

## Install Note:


Roof sealant should be expelled from both vents of the TopSpeed™ Mount as it is installed to assure the proper amount of roof sealant has been applied. If sealant is not expelled from all four vents, remove TopSpeed™ Mount, add more sealant to the cavity, then reinstall.



4) Loosen Course Adjustment bolt and adjust end Mounts up or down until aligned with bottom edge of array as marked on the roof, then tighten the Course Adjustment bolt.



5) To set the TopSpeed™ Mount level loosen the Leveling bolt and move the clamp up or down, then tighten the Leveling bolt and torque to 16 ft-lb.



6) Pull string line tight from one corner mount to opposite corner mount to align and level all TopSpeed™ Mounts between the end mounts.

## nstall Note:

Use the string line alignment feature on Mounts to level and align the Mounts.

## REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

**APPROVED** 


**Montgomery County** 

**Historic Preservation Commission** 


## **TopSpeed™ Mount Skirt Installation**

snapnrack.com


## **INSTALLATION INSTRUCTIONS**




7) Universal Spacers will need to be added to Mounts and Clamps where Skirt will be installed.



8) Install Universal Skirt by holding the skirt in Mount, sliding Skirt to align with array layout marks, and clamping skirt into mount.




9) Use TopSpeed™ Clamps to connect multiple lengths of Array Skirt.





Optionally use Universal Links to connect lengths of Array Skirt.



Montgomery County
Historic Preservation Commission

Kan Bulit


## **Required Tools**


Socket Wrench ■ Torque Wrench ■ 1/2" Socket ■ Electrician Tools


## **Materials Included**

## **Smart Clips**

- 1 (1) Smart Clip [(2) PV Wire, (1) Enphase IQ Cable]
- (1) Smart Clip XL [(6) PV Wire, (4) Enphase IQ]
- 3 (1) Wire Saver [(1) PV Wire]







Smart Clip XL

Wire Saver

**REVIEWED** 

By Laura DIPasquale at 2:20 pm, Jul 24, 2025


APPROVED

Montgomery County


Historic Preservation Commission

### **INSTALLATION INSTRUCTIONS - GROUND LUG**


The SnapNrack Ground Lug to be used in accordance with the National Electric Code, ANSI/NFPA 70.




1) Ground Lug (242-92202) can be attached anywhere along the module frame or any TopSpeed™ Mount near the Junction Box. Torque module clamping bolt to 8 ft-lb.



2) Run 10 - 6 AWG, solid, bare copper GEC into Ground Lug channel, torque wire clamping bolt to 8 ft-lb.



3) Run bare, solid EGC from Ground Lug R to Junction Box, bond bare EGC to stranded EGC in Junction Box. For details on installing the Junction Box reference the **Junction Box Installation Manual.** 



4) Optionally; Install Ground Lug on the Mount Landing Pad at the top of the array. Run bare copper between ground lug and Junction Box.

## **REVIEWED**

By Laura DIPasquale at 2:20 pm, Jul 24, 2025


APPROVED

Montgomery County


Historic Preservation Commission

### **INSTALLATION INSTRUCTIONS - SMART CLIPS**

SmartClip and SmartClip XL should be used to route conductors in a neat and workmanlike manner away from all non-bonded components and support the conductors adequately to eliminate potential damage.



1) Use SnapNrack Smart Clip II to manage up two PV wires inside the module frame while prepping out the modules on the ground or installing modules on the roof.



2) Use SnapNrack Smart Clip XL to manage larger bundles of PV wire; up to 6 PV wires per clip

\_\_

APPROVED

Montgomery County

Historic Preservation Commission

**REVIEWED** 

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

## **MLPE & RSD Installation**

snapnrack.com

## **Required Tools**

Socket Wrench Torque Wrench 1/2" Socket

### Materials Included - MLPE Rail Attachment Kit


1 (1) SnapNrack MLPE Frame Attachment Top


2 (1) SnapNrack MLPE Frame Attachment Bottom

3 (1) 5/16"-18 X 3/4" Serrated Flange Bolt SS

4 (1) SnapNrack Smart Clip

5 (1) SnapNrack MLPE Frame Attachment Coil Spring SS






## **Materials Included**

## SolarEdge Frame Mount


1 (1) SolarEdge Optimizer w/ Frame-Mounted Module Add-On



## **Enphase Frame Mount**

1 (1) Enphase Microinverter

(1) Enphase Frame Mount




## **REVIEWED**

By Laura DIPasquale at 2:20 pm, Jul 24, 2025


**APPROVED Montgomery County Historic Preservation Commission** 

### INSTALLATION INSTRUCTIONS - SNAPNRACK MLPE FRAME ATTACHMENT KIT


SnapNrack MLPE Frame Attachment kit are used to attach module level performance enhancing devices, and other devices such an SRD (rapid shutdown device), directly to module frames, and provide integrated grounding/bonding for Devices grounded through metal back plate. (Refer to the list of tested MLPE devices on page XX of this manual).



1) Slide the backplate channel of the MLPE device under the MLPE Frame Attachment Kit bolt. The MLPE mounting plate should rest against the MLPE mounting plate backstop on the MLPE Frame Attachment Kit.



2) Position the MLPE Frame Attachment Kit on the module frame flange in a location that will not interfere with mounting system components. The module frame flange should rest against the module flange backstop on the MLPE Frame Attachment Kit.




3) Tighten the mounting bolt on the MLPE Frame Attachment Kit to 12 lb-ft (144 lb-in).




### Install Note:


The MLPE Frame Attachment Kit bonds the following components: Module Frame, MLPE backplate and Smart Clip.



4) Connect the module leads to the input connectors on the MLPE device and manage conductors with the integrated Smart Clip.









Montgomery County **Historic Preservation Commission** 

Kare Bulit


### **INSTALLATION INSTRUCTIONS - SOLAREDGE FRAME MOUNT**



1) Locate the SolarEdge optimizer with Frame-Mounted Module Add-On at a location on the module frame that will not interfere with the TopSpeed™ Mounts.



2) Install the optimizer mounting plate onto the module frame and tighten hardware to 11 ft-lbs.




3) Connect the module leads to the input connectors on the optimizer and manage conductors with SnapNrack Smart Clips.


## Install Note:

If module is mounted in portrait, install MLPE on long side, short side for landscape.

### INSTALLATION INSTRUCTIONS - ENPHASE FRAME MOUNT




1) Locate the Enphase Frame Mount bracket clamp at a location on the module frame that will not interfere with the TopSpeed™ Mounts.



2) Slide the microinverter unit onto the bracket clamp, then move it slightly to the left.

## Install Note:

The microinverter mounting flange should be on the outside of the module frame.



- 3) Tighten the hardware to 13 ft-lbs.
- 4) Connect module leads to microinverter DC connectors.

## Install Note:

Refer to the Enphase Frame Mount installation guide for additional instructions.

**REVIEWED** 

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

**APPROVED** 

**Montgomery County** 

**Historic Preservation Commission** 

## **Module Installation**


snapnrack.com

## **Required Tools**

- Socket Wrench
- Torque Wrench
- 1/2" Socket
- Roofing Sealant


## **Materials Included**


- SnapNrack TopSpeed™ Mount
- ② SnapNrack TopSpeed™ Clamp



## **Other Materials Required**

- ② SnapNrack Smart Clip (2-5 per module) See Wire Management section for details
- ③ SnapNrack Smart Clip XL (10-20 per array) See Wire Management section for details





## **REVIEWED**

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

APPROVED

Montgomery County

Historic Preservation Commission

### **INSTALLATION INSTRUCTIONS - BOTTOM ROW**

### Recommended Best Practice:


Attach all TopSpeed™ mounts as the modules are being prepped with MLPEs on the ground. Attach Mounts before attaching MLPEs to simplify wire management.




## 🕜 Install Note:

It is recommended that module leads and connectors are prepared for installation using SnapNrack Smart Clips before being brought to the rooftop


- With no MLPE, secure module leads to module frame to allow access to connectors while modules are installed
- Secure MLPE device to module frame with SnapNrack MLPE Frame Attachment Kit and connect module leads to MLPE, and manage leads by positioning connectors to allow access during installation




1) Rest downslope edge of module on the Mounts and/or Clamps position module so side edge is flush with marked edge of array layout or Skirt.




2) Lower upslope edge of module while simultaneously applying slight pressure to seat module into Mounts and/or Clamps.





3) When module is level with roof verify the Speedseal™ portion of the TopSpeed™ Mounts are positioned entirely on one course of composition. If required listen the 1/2" nut and adjust the base as needed then tighten the bolt.



4) Lift the upslope edge of the module and fill the SpeedSeal™ reservoir with roofing sealant.

## Install Note:

Roof sealant should be expelled from both vents of the TopSpeed™ Mount as it is installed to assure the proper amount of roof sealant has been applied. If sealant is not expelled from all four vents, remove TopSpeed™ Mount, add more sealant to the cavity, then reinstall.


**APPROVED** Montgomery County

**Historic Preservation Commission** 


Kare Bulit

## REVIEWED


## **INSTALLATION INSTRUCTIONS - BOTTOM ROW**



5) Lower the module to the roof and drive the (4) pre installed Snapnrack #14 Wood Screws with 1/2" hex head into the roof sheathing.



6) Repeat steps 1 through 5 for additional modules in the array.



7) For staggered arrays and arrays with mixed orientation, use the TopSpeed™ Clamp as needed to support the modules.

When installing a TopSpeed™ Clamp for support of an over cantilevered module, the clamp shall be installed 2-6" from the edge of the upslope (cantilevered) module.

## 💇 Install Note:

Roof sealant should be expelled from both vents of the TopSpeed<sup>™</sup> Mount as it is installed to assure the proper amount of roof sealant has been applied. If sealant is not expelled from both vents, remove TopSpeed<sup>™</sup> Mount, add more sealant to the cavity, then reinstall.

## APPROVED

Montgomery County
Historic Preservation Commission


Kare Bulit

### **GROUND PATH DETAILS**

All TopSpeed™ components in the fault current ground path have been Certified to be used multiple times for grounding/bonding. The UL 2703 Listing does not specify a maximum number of uses for the Mount, Link, or Ground Lug. Review the requirements of the National Electrical Code (NEC) Article 250 to select the appropriate Equipment Grounding Conductor size based on the short-circuit current of the PV system.

When using Ground Lug R the following components are part of the fault current ground path:

- SnapNrack, TopSpeed™ Mount
- SnapNrack, TopSpeed™ Clamp





**EQUIPMENT GROUNDING** CONDUCTOR

**GROUND LUG** 




ARRAY SKIRT

## **GROUNDING METHOD DETAILS**





1) Row to row module bonding provided by bonding clips in Mount assembly and Clamp assembly.



2) Column to column bonding provided by Universal Skirt and bonding clips in the Clamp assembly and/or the RL Universal Link assembly.

Module heights evaluated for bonding with Link Bonding Clamps: 40mm, 38mm, 35mm, 32mm, 30mm






3) Each continuous array is connected to Equipment Grounding Conductor through Ground Lug (242-92202) installed on one module per array.

ptionally; Install Ground Lug on the

lount Landing Pad at the top of the



## **GROUNDING MARKING DETAILS**

The Ground Lug is marked with the ground symbol.

APPROVED

**Montgomery County Historic Preservation Commission** 

REVIEWED

# Maintaining the Grounding Bonding When Removing a Module

snapnrack.com

## INSTRUCTION FOR MAINTAINING THE GROUNDING BONDING WHEN REMOVING A MODULE FOR SERVICING

**CAUTION:** Module removal may disrupt the bonding path and could introduce the risk of electric shock. Additional steps may be required to maintain the bonding path. Modules should only be removed by qualified persons in compliance with the instructions in this manual.

Module removal is not presented as a frequently expected occurrence and will not be required as part of routine maintenance.

Scenarios that could result in a disruption of the bonding path are described, for example irregularly-shaped arrays, arrays consisting of individual rows, and any other scenario where module removal could disrupt the bonding path. In most cases, the removal of a module for servicing will not disturb or break grounding continuity. If a module is to be removed that will break continuity, these are the steps that must be taken to maintain a continuously bonded SnapNrack TopSpeed<sup>TM</sup> System.

## **Required Tools**

Socket Wrench


Torque Wrench

● 1/2" Socket

● 7/16" Socket

## **Required Materials**

- 1 #10 Or Larger Bare Copper Conductor
- 2 SnapNrack Ground Lug part no. 242-92202
- 3 Ilsco Part No. SGB-4
- 4 DnoRaxx Dynobond™



APPROVED

Montgomery County

Historic Preservation Commission

Kare Bulit


# Maintaining the Grounding Bonding When Removing a Module

snapnrack.com

### JUMPER ASSEMBLY INSTRUCTION & INSTALLATION

CAUTION: Do Not Remove the Module until the Jumper is installed

1) Identify the existing ground path at the location of module removal and choose an appropriate length of #10 bare copper to bridge the soon to be broken ground path.



Example of assembled bonding jumper using (2) SnapNrack Ground Lugs

- 2) Attach one ground lug to each end of #10 bare copper wire. See recommended options below:
- (2) SnapNrack Ground Lug part no. 242-922022
- 2. (2) Ilsco part no. SGB-4
- 3. (1) DroRaxx DynoBond™
- 3) Before the module is removed, attach the assembled bonding jumper. Depending on where the module will be removed and choice of ground lug, jumper attachment locations will vary.
  - SnapNrack Ground Lug part no. 242-92202 or Ilsco SGB-4 lugs can be attached to module frames or anywhere on the TopSpeed™ Mount.
  - DynoRaxx DynoBond™ is approved and appropriate when a short bonding jumper is needed from module to module.

4) Service the array. With the bonding jumper installed, it is now safe to remove the module for service or maintenance.

5) After Servicing the array reinstall the module and original ground path. Only then Remove the bonding jumper.

**Caution:** Do not remove the bonding jumper until original ground path is established.

### APPROVED

Montgomery County

Historic Preservation Commission

Kan Bulit

**REVIEWED** 

snapnrack.com

## APPROVED MODULE & MLPE INFORMATION

SnapNrack TopSpeed™ System has been tested with the following UL Listed module series: The SnapNrack TopSpeed™ System employs top-down clamps and links which have been evaluated for frame-to-system bonding, at specific mounting torques and with the specific module series listed below. All wattage values are covered.

Module manufacturer approval letters can be found at www.snapnrack.com.

Manufacturer	Model		
	DNA-120-MF23-XXX	DNA-120-BF26-XXXW	
	DNA-120-BF23-XXX	DNA-144-BF26-XXXW	
	DNA-144-MF23-XXX	DNA-108-BF10-xxxW	
Aptos Solar	DNA-144-BF23-XXX	DNA-120-BF10-xxxW	
	DNA-120-MF26-XXXW	DNA-108-MF10-xxxW	
	DNA-144-MF26-XXXW		
Boviet Solar	BVM7612M-XX	X-H-HC-BF-DG	
	CS6K-XXX-M	CS1H-XXX-MS	
	CS6K-XXX-M-SD	CS1H-XXX-MS-AB	
	CS6K-XXX-P	CS3W-XXX-P	
	CS6K-XXX-P-SD	CS3N-XXX-MS	
	CS6K-XXX-MS	CS1Y-XXX-MS	
Canadian Solar	CS3K-XXX-P	CS3W-MB-AG	
	CS3K-XXX-MS	CS3Y-MB-AG	
	CS3U-XXX-MS	CS6W-XXXMB-AG	
	CS3U-XXX-P	CS6R-XXXMS-HL	
	CS1K-XXX-MS	CS3W-XXX-MS	
CertainTeed	CTXXXHC11-06		
	CHSM6612M-XXX	CHSM72M-HC-XXX* (Astro 4)	
Chint Solar	CHSM6612M(BL)-XXX	CHSM72M-HC-XXX* (Astro 5)	
	CHSM6612M/HV-XXX		
	DH-M760B-XXXW	DH-M760F-XXXW	
Dehui Solar	DH-M760W-XXXW	DH-M772F-XXXW	
	DH-M772W-XXXW		
Freedom Forever	FF-MP-E	FF-MP-BBB-xxx	
	Q.PEAK DUO-G5-XXX	Q.PEAK DUO G10-XXX	
	Q.PEAK DUO-BLK-G5-XXX	Q.PEAK DUO BLK G10-XXX	
	Q.PLUS DUO-G5-XXX	Q.PEAK DUO G10+-XXX	
	Q.PEAK DUO-G7-XXX	Q.PEAK DUO BLK G10+-XXX	
	Q.PEAK DUO-BLK-G7-XXX	Q.PEAK DUO XL-G10.3-XXX	
Hanwha Q Cells	Q.PEAK DUO-G7.2-XXX	Q.PEAK DUO XL-G10.c-XXX	
	Q.PEAK DUO-G6+-XXX	Q.PEAK DUO XL-G10.d-XXX	
	Q.PEAK DUO-BLK-G6+-XXX	Q.PEAK DUO L-G8.3/BFG-XXX	
	Q.PEAK DUO-G6-XXX	Q.PEAK DUO L-G8.3/BGT-XXX	
	Q.PEAK DUO-BLK-G6-XXX	Q.PEAK DUO ML-G10-XXX	
	Q.PEAK DI APPROVED	PEAK DUO BLK ML-G10+-XXX	
	Q.PEAK DUC Montgomery Count	Q.PEAK DUO ML-G10+-XXX	

Historic Preservation Commission

## **REVIEWED**

Manufacturer	Model		
	Q.PEAK DUO-G8-XXX	Q.PEAK DUO BLK ML-G10-XXX	
	Q.PEAK DUO-BLK-G8-XXX	Q.PEAK DUO ML-G10-XXX	
	Q.PEAK DUO BLK-G6+/AC-XXX	Q.PEAK DUO BLK ML-G10.a+-XXX	
	Q.PEAK DUO-ML-G9-XXX	Q.PEAK DUO ML-G10.a-XXX	
	Q.PEAK DUO-BLK-ML-G9-XXX	Q.PEAK DUO BLK ML-G10.a-XXX	
	Q.PEAK DUO-BLK-G9-XXX	Q.PEAK DUO BLK G10+/AC XXX	
Hanwha Q Cells	Q.PEAK DUO-BLK-ML-G9+-XXX	Q.PEAK DUO BLK G10+/HL XXX	
	Q.PEAK DUO-ML-G9+-XXX	Q.PEAK DUO BLK ML-G10+/t-XXX	
	Q.PEAK DUO-BLK-ML-G9+-XXX	Q.PEAK DUO XL-G11.3 XXX	
	Q.PEAK DUO XL-G9.2-XXX	Q.PEAK DUO XL-G11.3 BFG XXX	
	Q.PEAK DUO XL-G9.3-XXX	Q.TRON-G1+ XXX	
	Q.PEAK DUO XL-G9.3/BFG-XXX	Q.TRON BLK-G1+ XXX	
	Q.PEAK DUO XL-G10.2-XXX	Q.TRON M-G2+ XXX	
	Q.PEAK DUO XL-G10.3/BFG-XXX	Q.TRON BLK M-G2+ XXX	
HT-SAAE	HT60-166M-XXX	HT60-182M-XXX	
Heliene	60M-XXX	72M-XXX	
	60P-XXX	72P-XXX	
// house de i	HiA-SXXXMS	HiS-SXXXYI	
"Hyundai (All may be followed by "BK")"	HiS-SXXXXY	HiS-SXXXYH(BK)	
Community and removal and a service and a se	HiN-Sx>	xXG(BK)	
Hyperion/Runergy	HY-DH108P8-XXX(Y)	HY-DH144N8-XXX	
nyperion/ kunergy	HY-DH144P8-XXX	HY-DH108N8-XXX	
	JAM60S09-XXX/PR	JAM72S10-XXX/PR	
	JAM60S10-XXX/MR	JAM72S12-XXX/PR	
IA Color	JAM60S10-XXX/PR	JAM60S17-XXX/MR	
JA Solar	JAM60S12-XXX/PR	JAM54S30-XXX/MR	
	JAM72S09-XXX/PR	JAM54S31-XXX/MR	
	JAM72S10-XXX/MR	JAM72D30-XXX/MB	
	JKMXXXM-60	JKMXXXP-72-V	
	JKMXXXM-60L	JKMXXXPP-72	
	JKMXXXM-60HL	JKMXXXPP-72-V	
	JKMXXXM-60HBL	JKMSXXXP-72	
	JKMXXXP-60	JKMXXXM-72HL-V	
	JKMXXXP-60-J4	JKMXXXM-72HL-TV	
Jinko Solar	JKMXXXP-60-V	JKMXXXM-72HBL	
	JKMXXXP-60B-J4	JKMXXXM-6TL3-B	
	JKMXXXPP-60	JKMXXXM-6RL3-B	
	JKMXXXPP-60-V	JKMXXXM-7RL3-V	
	JKMXXXM-72	JKMXXXM-7RL3-TV	
	JKMXXXM-72L-V	JKMXXXM-72HL4-V	
	JKMXXXP-72	JKMXXXM-72HL4-TV	
	LGXXXN1C-A5	LGXXXA1C-V5	
	LGXXXN1K-A5	LGXXXM1C-L5	
LG	LCVV	LGXXXM1K-L5	
	LGXX APPROVED	LGXXXN1C-N5	
	Montgomery Cour	ty LGAAANIC-N3	

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

Historic Preservation Commission

Manufacturer	Model		
	LGXXXS1C-A5	LGXXXN1K-L5	
	LGXXXN2C-B3	LGXXXN1K-A6	
	LGXXXN2W-B3	LGXXXN1C-A6	
	LGXXXN1C-G4	LGXXXN1W-A6	
	LGXXXN1K-G4	LGXXXQ1C-A6	
	LGXXXS1C-G4	LGXXXQ1K-A6	
	LGXXXN2C-G4	LGXXXM1K-A6	
	LGXXXN2K-G4	LGXXXM1C-A6	
LG	LGXXXN2W-G4	LGXXXA1C-A6	
	LGXXXS2C-G4	LGXXXQAC-A6	
	LGXXXS2W-G4	LGXXXQAK-A6	
	LGXXXN1C-V5	LGXXXN1K-B6	
	LGXXXN1W-V5	LGXXXN2W-E6	
	LGXXXN2T-V5	LGXXXN2T-E6	
	LGXXXN2T-J5	LGXXXN1K-E6	
	LGXXXN1T-V5	LGXXXN3K-V6	
	LR6-60-XXXM	LR4-60HPB-XXXM	
	LR6-60BK-XXXM	LR4-60HIB-XXXM	
	LR6-60HV-XXXM	LR4-60HPH-XXXM	
	LR6-60PB-XXXM	LR4-60HIH-XXXM	
Longi	LR6-60PE-XXXM	LR6-60HIH-XXXM	
	LR6-60PH-XXXM	LR6-60HIB-XXXM	
	LR6-60HPB-XXXM	LR4-72HPH-XXXM	
	LR6-60HPH-XXXM		
Meyer Burger	Meyer Burger Black*	Meyer Burger White*	
mSolar	TXI6-XX	(X120BB	
	MSEXXXSO5T	MSEXXXSQ4S	
	MSEXXXSO5K	MSEXXXSR8K	
	MSEXXXSQ5T	MSEXXXSR8T	
	MSEXXXSQ5K	MSEXXXSR9S	
Missien Celen	MSEXXXMM4J	MSE60AXXX	
Mission Solar	MSEXXXMM6J	MSEXXXSX5K	
	MSEXXXSO6W	MSEXXXSX5T	
	MSEXXXSO4J	MSEXXXSX6S	
	MSEXXXSO6J	MSEXXXSX6W	
	MSEXXXSQ6S	MSEXXXSX5R	
Navi Faarus Alliana	USNEA-XXXM3-60	USNEA-XXXM3-72	
Next Energy Alliance	USNEA-XXXM3B-60	USNEA-XXXM3B-72	
	VBHNXXXKA03	VBHXXXRA18N	
	VBHNXXXKA04	VBHXXXRA03K	
Panasonic	VBHNXXXSA17	EVPVXXX(K)	
	VBHNXXXSA18	EVPVXXXH	
	VBHN325SA17E	EVPVXXXPK	
	APPROVED		

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

APPROVED

**Montgomery County** 

Historic Preservation Commission

Manufacturer	Model		
	PS-M144(HCBF)-XXXW	PS-M108(HC)-XXXW	
Philadelphia Solar	PS-M108(HCBF)-XXXW		
	PSXXXM-20/U	PSxxxM8GF-18/VH	
	PSXXXMH-20/U	PSxxxM8GFH-18/VH	
Phono Solar	PSxxxM8GF-24/TH	PSxxxM6-24/TH	
	PSxxxM8GFH-24/TH		
	RECXXXTP2	RECXXXTP2SM 72 BLK2	
	RECXXXTP2-BLK	RECXXXAA	
	RECXXXNP	RECXXXTP3M	
REC	RECXXXTP2M	RECXXXTP4	
(All may be followed by "BLK" or	RECXXXTP2M 72	RECXXXAA Pure	
"BLACK")	RECXXXTP2M 72 BLK	RECXXXAA Pure-R	
	RECXXXTP2M 72 BLK2	RECXXXNP2	
	RECXXXTP2SM 72	RECXXXNP3	
	RECXXXTP2SM 72 BLK		
2-2-2-1	SEG-400-BMB-HV	SEG-xxx-BMD-HV	
SEG Solar	SEG-400-BMB-TB	SEG-xxx-BMD-TB	
	SLAXXX-M	SILXXXNT	
	SLAXXX-P	SILXXXHL	
	SSAXXX-M	SILXXXBK	
	SSAXXX-P	SILXXXNX	
	SILXXXBL	SILXXXNU	
Silfab	SILXXXML	SILXXXHC	
	SILXXXNL	SILXXXHN	
	SLGXXX-M	SILXXXBG	
	SLGXXX-P	SIL-xxxHC+	
	SSGXXX-M	SIL-xxxHM	
	SSGXXX-P		
	Solaria PowerXT-XXXR-PX	Solaria PowerXT-XXXR-PM	
Solaria	Solaria PowerXT-XXXR-BX	Solaria PowerXT-XXXR-PM-AC	
	Solaria PowerXT-XXXR-AC		
<u> </u>	SPR-AXXX-G-AC	SPR-MXXX-H-AC	
Sunpower	SPR-AXXX	SPR-MXXX	
Sunpower	SPR-AXXX-BLK-G-AC	SPR-MXXX-BLK-H-AC	
	SPR-AXXX-BLK	SPR-MXXX-BLK	
SunSpark	SST-XXXM3-60	SST-XXXM3-72	
Sanspan	SST-XXXM3B-60	SST-XXXM3B-72	
Talesun	TP660M-XXX	TP672M-XXX	
10100011	TP660P-XXX	TP672P-XXX	
	TS-BB54(XXX)	TS-BG60(XXX)	
Thornova	TS-BB60(XXX)	TS-BG72(XXX)	
	TS-BG54(XXX)		

By Laura DIPasquale at 2:20 pm, Jul 24, 2025



Montgomery County

Historic Preservation Commission

Kan Bulit

Manufacturer	Model		
	TSM-XXXDD05(II)	TSMXXXDD05H.05(II)	
	TSM-XXXDD05A.05(II)	TSM-XXXDD06M.05(II)	
	TSM-XXXDD05A.08(II)	TSM-XXXDE15H(II)	
	TSM-XXXDD05A.082(II)	TSM-XXXDE15M(II)	
	TSM-XXXPA05	TSMXXXDE06X.05(II)	
	TSM-XXXPA05.05	TSMXXXDE09.05	
	TSM-XXXPA05.08	TSM-XXXDE15V(II)	
Trina	TSM-XXXPD05	TSM-XXXDEG15VC.20(II)	
	TSM-XXXPD05.002	TSM-XXXDEG18MC.20(II)	
	TSM-XXXPD05.05	TSM-XXXDEG19C.20	
	TSM-XXXPD05.05S	TSM-XXXDEG21C.20	
	TSM-XXXPD05.08	TSM-XXXDE09C.05	
	TSM-XXXPD05.082	TSM-XXXDE09C.07	
	TSM-XXXPD05.08D	TSM-xxxNE09RC.05	
	TSM-XXXPD05.08S		
Vikram Solar	SOMERA VSMHBB.60.XXX.05	PREXOS VSMDHT.60.XXX.05	
VIKram Solar	SOMERA VSMH.72.XXX.05	PREXOS VSMDHT.72.XXX.05	
VCHN	VSUNXXX-144BMH-DG	VSUNXXX-108BMH	
VSUN	VSUNXXX-120BMH		
	ZXM6-60-XXX/M	ZXM6-NH144-XXXM	
ZNShine	ZXM6-NH120-XXXM	ZXM7-SH108-XXXM	
	ZXM7-SHLDD144-XXXM		

## SnapNrack TopSpeed™ has been tested with the following Module Level Power Electronic (MLPE) devices:

SnapNrack TopSpeed™ mounting systems has been tested with the following UL/NRTL Listed Module Level Power Electronic (MLPE) Devices. The back plates of the MLPEs have been evaluated for bonding to TopSpeed™ through the SnapNrack MLPE Frame Attachment Kit, model 242-02151.

MLPE Manufacturer	Model	
AP Smart	RSD-5	S-PLC
Celestica International	DG-006-F001201x DG-006-F001401x	
Delta Electronics	GPI00010105	
	C250	IQ7PLUS-72-2-US
	M215	IQ7PLUS-72-B-US
	M250	IQ8-60
Enphase	IQ6-60-2-US	IQ8PLUS-72
·	IQ6PLUS-72-2-US	IQ8A-72
	IQ7-60-2-US	IQ8H-208-72
	IQ7-60-B-US	IQ8H-240-72
Generec	S2502	
Ciulana Tankanlanian	Solis-F	RSD-1G
Ginlong Technologies	Solis-MLRSD-R1-1G	Solis-MLRSD-R2-1G

**REVIEWED** 



MLPE Manufacturer	Model		
	P300-5NC4ARS	P320-5NC4ARS	
	P370-5NC4AFS	P400-5NC4AFS	
	P320	P340	
	P370	P400	
	P401	P405	
SolarEdge	P485	P505	
	P730	P800p	
	P850	P860	
	P950	P1100	
	P1101	S440	
	\$500		
SMA	RSB-2S-US-10		
	TS4-R-F	TS4-R-M	
	TS4-R-O	TS4-R-S	
	TS4-R-M-DUO	TS4-R-O-DUO	
Tigo	TS4-R-S-DUO	TS4-A-F	
	TS4-A-2F	TS4-A-O	
	TS4-A-	·s	

snapnrack.com

The SnapNrack name and Snapl All information contained in this

**REVIEWED** 

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

**APPROVED** 

Montgomery County

Historic Preservation Commission

SNR\_TopSpeed Installation Manual\_v.1.5

## MSE PERC 108HC





Class leading power output

-0 to +3%



### FRAME-TO-FRAME WARRANTY

Degradation guaranteed not to exceed 2% in year 1 and 0.055% annually from years 2 to 25 with 84.8% capacity guaranteed in year 25. For more information, visit www.missionsolar.com/warranty

## CERTIFICATIONS







If you have questions or concerns about certification of our products in your area, please contact Mission Solar Energy.

C-MKTG-0033 VERSION: 2 VERSION DATE: 05/02/2024

## REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

# American solar built for the long haul

Mission Solar Energy is headquartered in San Antonio, Texas where we manufacture our modules. We produce American, high-quality solar modules ensuring the highest-in-class power output and best-in-class reliability. This product is tailored for residential and commercial applications. Every Mission Solar Energy solar module is certified and surpasses industry standard regulations, providing excellent performance over the long term.

## America's Module Company®



### **Fair Trade Practices**

- Free of forced labor at all stages of the supply chain
- Not subject to AD/CVD tariffs or investigations
- · Polysilicon manufactured with sustainable hydroelectric power



### Certified Reliability

- . Tested to UL 61730 & IEC Standards
- PID resistant
- · Resistance to salt mist corrosion



### Advanced Technology

- M10 half-cut cell with 10 busbars
- Passivated Emitter Rear Contact
- · Engineered for residential and commercial applications



## Extreme Weather Resilience

- · Up to 5,400 Pa snow and wind load
- . In-house hail tests exceeded 35 mm at 23 m/s



## **BAA Compliant for Government Projects**

- Buy American Act
- American Recovery & Reinvestment Act



## **APPROVED**

Montgomery County

**Historic Preservation Commission** 






www.missionsolar.com | info@missionsolar.com

## Class Leading 400-410W


## MSE PERC 108HC



## **CURRENT-VOLTAGE CURVE**

### MSE410HT0B: 410W, 108 HALF-CUT CELL SOLAR MODULE

 $Current-voltage\ characteristics\ with\ dependence\ on\ irradiance\ and\ module\ temperature$ 



### CERTIFICATIONS AND TESTS

IEC 61215, 61730, 61701 UL 61730



CEC



## Mission Solar Energy

 $8303\,S.\,New\,Braunfels\,Ave., San\,Antonio, Texas\,78235\\www.missionsolar.com \quad | \quad info@missionsolar.com$ 

Mission Solar Energy reserves the right to make specification changes without notice. C-MKTG-0033 VERSION: 2 VERSION DATE: 05/02/2024

## REVIEWED

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

ELECTRICAL SPECIFICATION					
PRODUCT TYPE	MSE	кххНТ	OB (xxx = F	max)	
Power Output	P <sub>max</sub>	$W_p$	400	405	410
Module Efficiency		%	20.5	20.7	21.0
Tolerance		%	0/+3	0/+3	0/+3
Short Circuit Current	Isc	Α	13.75	13.82	13.90
Open Circuit Voltage	Voc	V	37.09	37.27	37.41
Rated Current	Imp	Α	12.92	13.00	13.07
Rated Voltage	$V_{mp}$	V	30.96	31.16	31.38
Fuse Rating		Α	25A	25A	25A
System Voltage		٧	1,000	1,000	1,000

TEMPERATURE COEFF	ICIENTS
Normal Operating Cell Temperature (NOCT)	45.52°C (±3.7%)
Temperature Coefficient of Pmax	-0.343%/°C
Temperature Coefficient of Voc	-0.254%/°C
Temperature Coefficient of Isc	-0.257%/°C

OPERATING CONDITIONS		
Maximum System Voltage	1,000Vdc	
Operating Temperature Range	-40°F to 185°F (-40°C to +85°C)	
Maximum Series Fuse Rating	25A	
Fire Safety Classification	Type 1*	
Front & Back Load (UL Standard)	Up to 5,400 Pa front and 5,400 Pa back load. Tested to UL 61730	
Hail Safety Impact Velocity	25mm at 23 m/s	

 $^*Mission Solar Energy uses quality sourced materials that result in a Type 1 fire rating. Please note, the \\ 'Fire Class' Rating is designated for the fully-installed PV system, which includes, but is not limited to, the module, the type of mounting used, pitch and roof composition.$ 

MECHANICAL DATA		
Solar Cells	P-PERC 182mm x 182mm	
Cell Orientation	108 half-cut cells	
Module Dimension	1723mm x 1135mm x 35mm	
Weight	42 lbs. (19kg)	
Front Glass	3.2mm tempered, low-iron, anti-reflective	
Frame	35mm anodized interlocking	
Encapsulant	Ethylene vinyl acetate (EVA)	
Junction Box	Protection class IP68 with 3 bypass-diodes	
Cable	1.2m, Wire 4mm² (12AWG)	
Connector	MC4 Staubli PV-KBT4/6II-UR and PV-KST4/6II-UR	

S	HIPPING	INFOR	MATIO	7
ontainer Feet	Ship To	Pallets	Panels	410W Bin
53'	Most States	26	806	330.46 kW

PALLET [31 PANELS]				
Weight 1,610 lbs. (730 kg)	Height 51 in (129.5 cm)	Width 47 in (119.4 cm)	Length 70 in (119.4 cm)	

Double Stack: (Horizontal Orientation): 31 panels per pallet

### **APPROVED**

Montgomery County

Historic Preservation Commission

Kare Bulit

www.missionsolar.com | info@missionsolar.com



## IQ8 and IQ8+ Microinverters


Our newest IQ8 Microinverters<sup>1, 2, 3</sup> are the industry's first microgridforming<sup>4</sup>, software-defined microinverters with split-phase power conversion capability to convert DC power to AC power efficiently.







Key specifications	IQ8-60-M-US	IQ8PLUS-72-M-US
Peak output power	245 VA	300 VA
Nominal grid voltage (L-L)	240 V, split-ph	ase (L-L), 180°
Nominal frequency	60 Hz	60 Hz
CEC weighted efficiency	97%	97%
Maximum input DC voltage	50 V	60 V
MPPT voltage range	27-37 V	27-45 V
Maximum module I <sub>sc</sub>	20 A	20 A
Ambient temperature range	-40°C to 60°C	–40°F to 140°F)



## 

- Lightweight and compact with plug-and-play connectors
- Power line communication (PLC) between components
- Faster installation with simple twowire cabling

### (V) Reliable

- Produce power even when the grid is down
- More than one million cumulative hours of testing
- Industry-leading limited warranty of up to 25 years
- Class II double-insulated enclosure
- Optimized for the latest highpowered PV modules

## Microgrid-forming

- Compliant with the latest advanced grid support<sup>5</sup>
- Remote automatic updates for the latest grid requirements
- Configurable to support a wide range of grid profiles
- Meets CA Rule 21 (UL 1741-SA) and IEEE 1547:2018 (UL 1741-SB 3rd Ed.)

REVIEWED By Laura DIPasquale at 2:20 pm, Jul 24, 2025

**APPROVED** Montgomery County

**Historic Preservation Commission** 

<sup>&</sup>lt;sup>1</sup> IQ8 Series Microinverters can be added to existing IQ7 systems on the same IQ Gateway only in the following grid-tied configurations: Solar Only or Solar + Battery (IQ Battery 3T/10T and IQ Battery 5P) without backup.  $^2$  IQ7 Series Microinverters cannot be added to a site with existing IQ8 Series Microinverters or

Mixed system of IQ7 and IQ8 will not support IQ8-specific PCS features and grid-forming cap

<sup>&</sup>lt;sup>3</sup> IQ Microinverters ship with default settings that meet North America's IEEE 1547 interconne requirements. Region-specific adjustments may be requested by an Authority Having Jurisd representative, according to the IEEE 1547 interconnection standard. Use an IQ Gateway to

Input data (DC)	Units	IQ8-60-M-US	IQ8PLUS-72-M-US
Commonly used module pairings <sup>6</sup>	W	235-350	235-440
Module compatibility	_	To meet compatibility, PV modules must be within maximum input DC voltage and maximum module I <sub>sc</sub> . Module compatibility can be checked at <a href="https://enphase.com/installers/microinverters/calculator">https://enphase.com/installers/microinverters/calculator</a> .	
MPPT voltage range	V	27–37	27-45
Operating range	V	16-48	16-58
Minimum/Maximum start voltage	٧	22/48	22/58
Maximum input DC voltage	٧	50	60
Maximum continuous input DC current	Α	10	12
Maximum input DC short-circuit current	А	25	
Maximum module I <sub>sc</sub>	Α	20	
Overvoltage class DC port	_	1	I
DC port backfeed current	mA		)
PV array configuration	_	Ungrounded array; no additional DC side protection required; AC side protection requires maximum 20 A per branch circuit.	

Output data (AC)	Units	IQ8-60-M-US	IQ8PLUS-72-M-US
Peak output power	VA	245	300
Maximum continuous output power	VA	240	290
Nominal grid voltage (L-L)	V	240, split-phase (L-L), 180°	
Minimum and Maximum grid voltage <sup>7</sup>	٧	211-264	
Maximum continuous output current	Α	1.0	1.21
Nominal frequency	Hz	6	0
Extended frequency range	Hz	47-	-68
AC short-circuit fault current over three cycles	Arms	2	2
Maximum units per 20 A (L-L) branch circuit <sup>8</sup>	_	16	13
Total harmonic distortion	%	<5	
Overvoltage class AC port	-	III	
AC port backfeed current	mA	30	
Power factor setting	_	1.0	
Grid-tied power factor (adjustable)	_	0.85 leading 0.85 lagging	
Peak efficiency	%	97	7.7
CEC weighted efficiency	%	9	7
Nighttime power consumption	mW	23	25

Mechanical data

Ambient temperature range

APPROVED

Montgomery County

Historic Preservation Commission

IQ8PLUS-72-M-US 40°F to 140°F)

**REVIEWED** 

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

Mechanical data	IQ8-60-M-US	IQ8PLUS-72-M-US
Relative humidity range	4% to 100% (condensing)	
DC connector type	Stäubli MC4	
Dimensions (H × W × D) 212 mm (8.3 in) × 175 mm (6.9 in) × 30.2 mm (1.2 in)		(6.9 in) × 30.2 mm (1.2 in)
Weight	1.1 kg (2	2.43 lb)
Cooling	Natural convection—no fans	
Approved for wet locations	Ye	es
Pollution degree	PI	03
Enclosure	Class II double-insulated, corrosi	on-resistant polymeric enclosure
Environmental category/UV exposure rating	NEMA Type 6/Outdoor	

Compliance	IQ8-60-M-US	IQ8PLUS-72-M-US
Certifications	15 Class B, ICES-0003 Class B	ems, for AC and DC conductors, when

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

APPROVED

Montgomery County

Historic Preservation Commission

## Components of the Enphase Energy System



### **IQ** Battery

All-in-one AC-coupled storage solution that integrates seamlessly with your solar energy system, providing reliable backup power and intelligent energy management for maximum performance and energy savings.



## **IQ System Controller**

The IQ System Controller connects the home to the grid power, IQ Batteries, generator and solar PV with microinverters.



### IQ Combiner/IQ Gateway

The IQ Combiner/IQ Gateway is a device that performs energy management, provides internet connectivity, and integrates with the IQ Series Microinverters to provide complete control and insights into the Enphase Energy System.



### IQ Cable

The IQ Cable is a continuouslength 12-AWG cable with pre-installed connectors for IQ Microinverters that support faster, simpler, and more reliable installations. The cable is handled like standard outdoorrated electrical wire, allowing it to be cut, spliced, and extended as needed.

**REVIEWED** 

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

APPROVED

Montgomery County

**Historic Preservation Commission** 

Kan Bulit

## Revision history

Revision	Date	Description
DSH-00206-4.0	December 2024	Updated information on backward compatibility with IQ7 Series Microinverters.
DSH-00206-3.0	February 2024	Updated the information about IEEE 1547 interconnection standard requirements.
DSH-00206-2.0	October 2023	Included NEC 2023 specification in the "Compliance" section.
DSH-00206-1.0	September 2023	Initial release.

**REVIEWED** 

By Laura DIPasquale at 2:20 pm, Jul 24, 2025

APPROVED

Montgomery County

Historic Preservation Commission